

FAQ FACT SHEET

RUTLAND CITY-PROCTOR STP 2728(1)

RUTLAND CITY NH 2716(1)

RUTLAND CITY STP 019-3(57)

The information presented here is part of the contract between Peckham Road Corporation and VTrans. The information is being provided to help answer questions regarding the work to be done on South Main Street (US Route 7), Woodstock Avenue (US Route 4), and West Street (US Business Route 4) in the City of Rutland, and South Street and East Street (VT Route 3) in Proctor. The work is anticipated to happen during the 2014 Construction season, starting in April and ending in October. The information provided is based on current schedules and contract work. Changes may occur during the construction season. Information will be updated throughout the construction season to reflect any changes that may occur.

COMPLETION DATES/TIMES:

- 1. The anticipated completion written date October 31st, 2014 ; if there are delays that make this impossible, details will be posted on this website.*
- 2. The Woodstock Avenue (US Route 4) portion of the project has an interim completion date of May 1st, 2014 for the alternate Bike Lane pavement markings work.*
- 3. The Woodstock Avenue alternate Bike Lane pavement markings work will not start prior to April 1st, 2014 and is authorized to be done during daytime hours.*
- 4. The Woodstock Avenue alternate Bike Lane pavement markings configuration (consisting of one travel lane eastbound, one travel lane west bound, a Two Way Left Turn Lane in the center, and a bike lane on each curb line) is intended to remain in place for a minimum of 30 days, but can be shorter if the City determines the continuance of the alternate pavement marking configuration is undesirable or unsafe.”*
- 5. All other Rutland City work is nighttime. Nighttime is defined as 6:00 PM-6:00 AM*
- 6. Proctor work will be daytime work.*

HISTORICAL/ENVIRONMENTAL:

- 7. The line of large cobbles located along the west and south edges of Court Sq. will be kept.*
- 8. Any retaining walls impacted by the project will be repaired or replaced in-kind.*
- 9. Existing marble curbing on West St. between Church and Elm will be preserved, or repaired and reset.*
- 10. Impacts to marble paving stones shall be minimized; if necessary to remove, they will be reset or reused.*
- 11. Outdoor concrete steps leading from residences to the sidewalk shall be preserved or replaced in kind.*
- 12. Marble steps in front of Armory are to be preserved.*
- 13. All historic fencing in the project shall be retained.*
- 14. Marble hitching posts between the library and Center St. will be retained.*
- 15. All drives will be paved with an apron extending a minimum of 4 feet into the drive from the outside edge of the highway shoulder.*

TRAFFIC MANAGEMENT:

- 16. Minimum of one way traffic at all times; during holiday periods-2 way Traffic*
- 17. Delays shall not be more than 10 min unless otherwise directed by the Engineer.*
- 18. What are video detection systems?*
Video detection systems are overhead cameras mounted on a signal pole solely for the purpose of detecting the presence of vehicles in order to provide the best distribution of green light time based on traffic demand. They are cost-effective replacements for the existing systems which are in-ground induction loops cut into the road surface.

MISCELLANEOUS:

- 19. No work will happen during the follow holiday periods: Memorial Day, July 4th, Labor Day. The holiday period is defined as 12:00 noon the day before the holiday and extending until 7:00 AM the day after the holiday period. This period will extend through the weekend if the holiday is on Saturday or Sunday.*

20. *The following events are occurring in the Main Street Park:*

Family Fun Day, Sunday, June 15th, 7:00 AM-5:00 PM

City Band concerts, Sunday, June 16th to August 18th, 6:00-9:00 PM

Wednesday Night concerts, June 19th to August 21st, 6:00-9:00 PM

*Art in the Park, Friday-Sunday, August 9th-11th and October 11th -13th
Times: Friday—3:00-9:00 PM; Sat/Sun 7:00 AM-9:00 PM*

The contractor's work will be scheduled to minimize impacts to these events.

21. *As a taxpayer, How can I ask additional questions ?*

You can call or email Project Outreach Coordinator Natalie Boyle. She can be reached at (802)310-7822 or nboyle@gpinet.com

22. *How can I have input? Feel free to call or email Natalie Boyle.*

Additionally, you may comment on our Facebook page at www.facebook.com/RutlandCityProctor2014

23. *Who pays the time for the Sherriff and the police to be out there?*

The Sherriff and Police that are providing traffic control for the contractor's operations are paid for by the project.

24. *What is the general breakdown of the cost of this project? How much is the city, state, federal portion?*

The cost break down is as follows with portions:

- *South Main Street water work:*

\$3,924,290.18

80% Federal

10% State

10% Local

- *WoodStock Ave. & South Main St. Pave:*

\$2,767,894.90

81% Federal

19% State

- *West Street and Vt Route 3 Pave:*

\$3,243,300.99

81% Federal

19% State

25. *Where do I apply if I want a job?*

Peckham Road Corp, Haarlem Ave. #200, White Plains, NY 10603

26. *Does the contractor get penalized if the project is not completed on time?*

27. *Who do I contact if I have a concern about how a specific detail of the project will affect my property?*

Contact Tim Pockette, Resident Engineer. Tim.pockette@state.vt.us; 802.793.4027