

INVITATION FOR BIDS

Submitted bids will be publicly announced starting at 11:00 a.m. prevailing time on Friday, **June 08, 2018**; at VTrans, One National Life Drive, Montpelier, VT. The time of receiving and opening bids may be postponed due to emergencies or unforeseen conditions.

MANCHESTER STP 2970 (1) - BEGINNING AT A POINT IN THE VILLAGE OF MANCHESTER ON VT ROUTE 7A AT MILE MARKER 2.409 = STA M 127+19.52 AND EXTENDING NORTHERLY FOR A DISTANCE OF APPROXIMATELY 26,484.48 FEET (5.016 MILES) AND ENDING AT A POINT IN THE TOWN OF MANCHESTER ON VT ROUTE 7A AT MILE MARKER 7.425 = STA M 392+04.00.

ALSO BEGINNING AT A POINT IN THE TOWN OF MANCHESTER ON VT ROUTE 11 AT MILE MARKER 0.000 = STA D 0+00.00 AND EXTENDING EASTERLY FOR A DISTANCE OF APPROXIMATELY 6,689.76 FEET (1.267 MILES) AND ENDING AT A POINT IN THE TOWN OF MANCHESTER ON VT ROUTE 11 AT MILE MARKER 1.267 = STA D 66+89.76.

ALSO BEGINNING AT A POINT IN THE TOWN OF MANCHESTER ON VT ROUTE 30 AT MILE MARKER 0.008 = STA B 0+40.04 AND EXTENDING NORTHERLY FOR A DISTANCE OF APPROXIMATELY 1,633.72 FEET (0.309 MILES) AND ENDING AT A POINT IN THE TOWN OF MANCHESTER ON VT ROUTE 30 AT MILE MARKER 0.317 = STA B 16+73.76. TOTAL LENGTH OF PROJECT 34,807.96 FEET (6.592 MILES)

WORK TO BE PERFORMED UNDER THIS PROJECT INCLUDES: COLD PLANING AND PAVING WITH A LEVELING COURSE AND A WEARING COURSE, OVERLAY WITH A WEARING COURSE, PAVEMENT MARKINGS, SIGNS, DRAINAGE IMPROVEMENT, A HIGHWAY-RAILROAD GRADE CROSSING RECONSTRUCTION AND RAIL SIGNAL IMPROVEMENTS, STOP BAR DETECTION, PEDESTRIAN SIGNAL SYSTEM MODIFICATIONS, AND OTHER HIGHWAY RELATED ITEMS.

MANCHESTER STP BP15 (5) - ON DEPOT STREET (VERMONT ROUTE 11 / 30, TOWN HIGHWAY 3) APPROXIMATELY 250 FEET EAST OF THE MAIN STREET ROUNDABOUT (VERMONT ROUTE 7A, TOWN HIGHWAY 1) CONTINUING EASTERLY TO THE INTERSECTION OF DEPOT STREET AND HIGHLAND AVENUE (TOWN HIGHWAY 8).

WORK TO BE PERFORMED UNDER THIS PROJECT INCLUDES: CONSTRUCTION OF NEW CURBS AND DRAINAGE FEATURES, AND CONNECTING INTO THE EXISTING DRAINAGE SYSTEM; INSTALLATION OF TREE PITS AND GREEN STRIPS; PLANTING TREES, SHRUBS, AND PERENNIALS AND ESTABLISHING TURF; RECONSTRUCTION OF SIDEWALK SECTIONS TO MEET ADA STANDARDS; INSTALLATION OF STREET LIGHTING CONDUIT, STREET LIGHTING BASES, POLES, LUMINAIRES, AND ELECTRICAL METERS; AND ASSOCIATED INCIDENTAL CONSTRUCTION FEATURES. THE PROJECT IS INTENDED TO BE COMPLETED PRIOR TO PLACEMENT OF THE TOP WEARING COURSE OF THE STATE PAVING PROJECT MANCHESTER STP 2970 (1). STATE PAVING PROJECT MANCHESTER STP 2970 (1) SHALL INCLUDE THE TOP WEARING COURSE, FINAL PAVEMENT MARKINGS, COLD PLANING AND CROWN SHIFT, AND SIGNS. LENGTH OF PROJECT STATION D 2+79 - D 31+91 2912 FEET (0.552 MILES).

CONTRACT COMPLETION DATE: The Contract shall be completed on or before **June 28, 2019**.

BID BOND: Electronic bid bond to be submitted in the amount of 5% of the Contractor's bid.

ENGINEER'S ESTIMATE: For this proposal the Engineer's Estimate is Category E.

PLANS AND PROPOSALS MAY BE OBTAINED AT NO COST BY: Clicking on the following link then selecting and submitting the "Request For Plans" form for the project you are requesting.
<http://vtrans.vermont.gov/contract-admin/construction/advertised-projects>

QUESTIONS: During the advertisement period for this proposal, all questions shall be addressed solely to the Office of Contract Administration via e-mail: AOT.ConstructionContractingInquiry@vermont.gov

PREQUALIFICATION OF CONTRACTORS: All bidders on this project must hold both current annual Prequalification with the Vermont Agency of Transportation through the "Contractor's Experience Questionnaire and Financial Statement" and unconditioned project-specific approval through the "Standard Form - Request for Proposal" CA-82 form. These documents are available at: <http://vtrans.vermont.gov/sites/aot/files/contractadmin/documents/PreQualCA82.pdf>

JOINT VENTURES: Two or more Prequalified entities may combine all or a portion of their assets, equipment, personnel, and experience for the purpose of bidding on a single Agency contract by providing a written request to obtain Contract Specific Prequalification as a Joint Venture for a specific contract. Please refer to section 5.07 of the Policies and Procedures on Prequalification, Bidding and Award of Contracts, available at: <http://vtrans.vermont.gov/contract-admin/construction>

STANDARD SPECIFICATIONS: The work under this Contract shall be performed in accordance with the 2011 STANDARD SPECIFICATIONS FOR CONSTRUCTION, as modified. The Standard Specifications are available on the VTrans website. <http://vtrans.vermont.gov/contract-admin/construction/2011-standard-specifications>

MINIMUM LABOR AND TRUCK RATES: For the project are included in the advertised specification and bid proposal and such rates shall be a part of the Contract for this project.

NON-COLLUSION AFFIDAVIT: All bidders will be required to execute a sworn statement, certifying that the bidder has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with such Contract.

NONDISCRIMINATION IN AGENCY CONTRACTS: VTrans hereby notifies all bidders that it will insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, sex, or national origin in consideration for an award.

NOTICE TO BIDDERS-MANDATORY ELECTRONIC BIDDING: Bidders are hereby notified that only two-way electronic bids will be accepted by the Agency for this proposal. For information on electronic bidding with the Agency, please visit our website at <http://vtrans.vermont.gov/contract-admin/construction/electronic-bidding>

RAILROAD PROTECTIVE LIABILITY INSURANCE. Prospective Bidders/Contractors are hereby notified that Railroad Protective Liability Insurance is required for this Contract in accordance with Subsection 103.04(d) of the 2011 STANDARD SPECIFICATIONS FOR CONSTRUCTION. The Railroad Protective Liability Form is not included in the Proposal. The form will be provided by the successful Bidder's insurance company.

TELECOMMUNICATIONS RELAY SERVICE

TTY/TDD 1-800-253-0191

APPROXIMATE ESTIMATE OF QUANTITIES

ITEM NO.	LINE NO.	DESCRIPTION	QUANTITY	UNITS
201.30	0005	THINNING AND TRIMMING	0.100	ACRE
201.31	0010	THINNING AND TRIMMING FOR SIGNS	15.000	EACH
203.15	0015	COMMON EXCAVATION	1,300.000	CY
203.16	0020	SOLID ROCK EXCAVATION	70.000	CY
203.30	0025	EARTH BORROW	410.000	CY
204.20	0030	TRENCH EXCAVATION OF EARTH	390.000	CY
204.22	0035	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.) (STP 2970(1))(VT 11)	1.000	CY
204.22	0040	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.) (STP 2970(1))(VT 30)	1.000	CY
204.22	0045	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.) (STP 2970(1))(VT 7A)	1.000	CY
204.22	0050	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.) (STP BP15(5))	1.000	CY
204.30	0055	GRANULAR BACKFILL FOR STRUCTURES	270.000	CY
210.10	0060	COLD PLANING, BITUMINOUS PAVEMENT	102,900.000	SY
301.28	0065	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	500.000	TON
301.35	0070	SUBBASE OF DENSE GRADED CRUSHED STONE	560.000	CY
406.50	0075	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.) (STP 2970(1))(VT 11)	1.000	LU
406.50	0080	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.) (STP 2970(1))(VT 30)	1.000	LU
406.50	0085	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.) (STP 2970(1))(VT 7A)	1.000	LU
406.50	0090	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.) (STP BP 15(5))	1.000	LU
490.30	0095	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 70-28)(SBS POLYMER)	13,900.000	TON
490.31	0100	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.) (STP 2970(1))(VT 11)	1.000	LU
490.31	0105	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.) (STP 2970(1))(VT 30)	1.000	LU

ITEM NO.	LINE NO.	DESCRIPTION	QUANTITY	UNITS
490.31	0110	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.) (STP 2970(1))(VT 7A)	1.000	LU
514.10	0115	WATER REPELLENT, SILANE	7.000	GAL
516.10	0120	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	220.000	LF
580.20	0125	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	60.000	CF
601.0915	0130	18" CPEP	208.000	LF
601.0920	0135	24" CPEP	24.000	LF
604.20	0140	PRECAST REINFORCED CONCRETE CATCH BASIN WITH CAST IRON GRATE	8.000	EACH
604.40	0145	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	4.000	EACH
604.412	0150	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	90.000	EACH
604.415	0155	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	11.000	EACH
604.418	0160	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	11.000	EACH
604.42	0165	CHANGING ELEVATION OF SEWER MANHOLES	36.000	EACH
605.10	0170	6 INCH UNDERDRAIN PIPE	255.000	LF
605.20	0175	6 INCH UNDERDRAIN CARRIER PIPE	20.000	LF
608.15	0180	POWER GRADER RENTAL	40.000	HR
608.25	0185	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	140.000	HR
608.30	0190	POWER BROOM RENTAL, TYPE I	50.000	HR
608.31	0195	POWER BROOM RENTAL, TYPE II	85.000	HR
608.37	0200	TRUCK RENTAL	280.000	HR
608.40	0205	LOADER RENTAL, TYPE I	40.000	HR
616.21	0210	VERTICAL GRANITE CURB	1,570.000	LF
616.28	0215	CAST-IN-PLACE CONCRETE CURB, TYPE B	20.000	LF
616.40	0220	REMOVING AND RESETTING CURB	380.000	LF
616.41	0225	REMOVAL OF EXISTING CURB	40.000	LF
616.47	0230	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	22.000	TON
618.10	0235	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	520.000	SY
618.11	0240	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	150.000	SY
618.30	0245	DETECTABLE WARNING SURFACE	430.000	SF
619.17	0250	YIELDING MARKER POSTS	20.000	EACH
621.20	0255	STEEL BEAM GUARDRAIL, GALVANIZED	1,687.500	LF
621.60	0260	ANCHOR FOR STEEL BEAM RAIL	12.000	EACH
621.80	0265	REMOVAL AND DISPOSAL OF GUARDRAIL	1,660.000	LF
622.10	0270	INSULATION BOARD	3.000	MFBM
629.20	0275	ADJUST ELEVATION OF VALVE BOX	58.000	EACH
630.10	0280	UNIFORMED TRAFFIC OFFICERS	2,600.000	HR
630.15	0285	FLAGGERS	9,850.000	HR
631.10	0290	FIELD OFFICE, ENGINEERS	1.000	LS
631.16	0295	TESTING EQUIPMENT, CONCRETE	1.000	LS
631.17	0300	TESTING EQUIPMENT, BITUMINOUS	1.000	LS
631.26	0305	FIELD OFFICE TELEPHONE (N.A.B.I.)	3,000.000	DL
634.10	0310	EMPLOYEE TRAINEESHIP	520.000	HR
635.11	0315	MOBILIZATION/DEMOBILIZATION (STP 2970(1))(VT 11)	1.000	LS
635.11	0320	MOBILIZATION/DEMOBILIZATION (STP 2970(1))(VT 30)	1.000	LS
635.11	0325	MOBILIZATION/DEMOBILIZATION (STP 2970(1))(VT 7A)	1.000	LS
641.10	0330	TRAFFIC CONTROL (STP 2970(1))(VT 11)	1.000	LS
641.10	0335	TRAFFIC CONTROL (STP 2970(1))(VT 30)	1.000	LS
641.10	0340	TRAFFIC CONTROL (STP 2970(1))(VT 7A)	1.000	LS
641.15	0345	PORTABLE CHANGEABLE MESSAGE SIGN	6.000	EACH
646.4011	0350	DURABLE 4 INCH WHITE LINE, TYPE A TAPE	4,200.000	LF
646.404	0355	DURABLE 4 INCH WHITE LINE, POLYUREA	63,100.000	LF

ITEM NO.	LINE NO.	DESCRIPTION	QUANTITY	UNITS
646.4111	0360	DURABLE 4 INCH YELLOW LINE, TYPE A TAPE	400.000	LF
646.414	0365	DURABLE 4 INCH YELLOW LINE, POLYUREA	74,300.000	LF
646.4211	0370	DURABLE 6 INCH WHITE LINE, TYPE A TAPE	600.000	LF
646.424	0375	DURABLE 6 INCH WHITE LINE, POLYUREA	4,500.000	LF
646.4411	0380	DURABLE 8 INCH WHITE LINE, TYPE A TAPE	2,800.000	LF
646.4511	0385	DURABLE 8 INCH YELLOW LINE, TYPE A TAPE	2,850.000	LF
646.4611	0390	DURABLE 12 INCH WHITE LINE, TYPE A TAPE	430.000	LF
646.4811	0395	DURABLE 24 INCH STOP BAR, TYPE A TAPE	490.000	LF
646.4914	0400	DURABLE LETTER OR SYMBOL, TYPE D TAPE	219.000	EACH
646.5011	0405	DURABLE CROSSWALK MARKING, TYPE A TAPE	1,550.000	LF
646.5114	0410	DURABLE RAILROAD CROSSING SYMBOL, TYPE D TAPE	2.000	EACH
646.602	0415	TEMPORARY 4 INCH WHITE LINE, PAINT	140,170.000	LF
646.612	0420	TEMPORARY 4 INCH YELLOW LINE, PAINT	155,715.000	LF
646.622	0425	TEMPORARY 6 INCH WHITE LINE, PAINT	10,100.000	LF
646.652	0430	TEMPORARY 8 INCH YELLOW LINE, PAINT	1,060.000	LF
646.662	0435	TEMPORARY 12 INCH WHITE LINE, PAINT	850.000	LF
646.682	0440	TEMPORARY 24 INCH STOP BAR, PAINT	1,060.000	LF
646.692	0445	TEMPORARY LETTER OR SYMBOL, PAINT	479.000	EACH
646.702	0450	TEMPORARY CROSSWALK MARKING, PAINT	3,187.000	LF
646.712	0455	TEMPORARY RAILROAD CROSSING SYMBOL, PAINT	4.000	EACH
646.76	0460	LINE STRIPING TARGETS	14,000.000	EACH
646.85	0465	REMOVAL OF EXISTING PAVEMENT MARKINGS	6,480.000	SF
649.21	0470	GEOTEXTILE UNDER RAILROAD BALLAST	675.000	SY
649.31	0475	GEOTEXTILE UNDER STONE FILL	70.000	SY
649.41	0480	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	460.000	SY
651.15	0485	SEED	120.000	LB
651.18	0490	FERTILIZER	580.000	LB
651.20	0495	AGRICULTURAL LIMESTONE	3.000	TON
651.25	0500	HAY MULCH	3.000	TON
651.35	0505	TOPSOIL	100.000	CY
653.41	0510	INLET PROTECTION DEVICE, TYPE II	32.000	EACH
656.30	0515	DECIDUOUS TREES (AMELANCHIER LAEVIS)(B & B) (2")	9.000	EACH
656.30	0520	DECIDUOUS TREES (CELTIS OCCIDENTALIS)(B & B) (3")	9.000	EACH
656.30	0525	DECIDUOUS TREES (GLEDITSIA TRIACANTHOS VAR "SHADEMASTER")(B & B)(3")	3.000	EACH
656.30	0530	DECIDUOUS TREES (GLEDITSIA TRIACANTHOS VAR "IMPERIAL") (B & B)(3")	6.000	EACH
656.30	0535	DECIDUOUS TREES (QUERCUS RUBRA)(B & B)(3")	3.000	EACH
656.80	0540	LANDSCAPE BACKFILL, TRUCK MEASUREMENT	200.000	CY
675.20	0545	TRAFFIC SIGNS, TYPE A	1,583.000	SF
675.341	0550	SQUARE TUBE SIGN POST AND ANCHOR	3,600.000	LF
675.50	0555	REMOVING SIGNS	425.000	EACH
675.60	0560	ERECTING SALVAGED SIGNS	19.000	EACH
676.10	0565	DELINEATOR WITH STEEL POST	12.000	EACH
678.21	0570	ELECTRICAL CONDUIT (2")(SCH 80 PVC)	1,360.000	LF
678.23	0575	WIRED CONDUIT (2")(SCH 80 PVC)	235.000	LF
678.30	0580	ELECTRICAL CONDUIT SLEEVE (6")(STEEL)	110.000	LF
679.55	0585	POWER DROP STANCHION, STREET LIGHTING	3.000	EACH
690.50	0590	PRICE ADJUSTMENT, FUEL (N.A.B.I.) (STP 2970(1))(VT 11)	1.000	LU
690.50	0595	PRICE ADJUSTMENT, FUEL (N.A.B.I.) (STP 2970(1))(VT 30)	1.000	LU
690.50	0600	PRICE ADJUSTMENT, FUEL (N.A.B.I.) (STP 2970(1))(VT 7A)	1.000	LU
690.50	0605	PRICE ADJUSTMENT, FUEL (N.A.B.I.) (STP BP 15(5))	1.000	LU

ITEM NO.	LINE NO.	DESCRIPTION	QUANTITY	UNITS
900.608	0610	SPECIAL PROVISION (LANDSCAPE COBBLES)	20.000	CY
900.615	0615	SPECIAL PROVISION (MAINTENANCE OF RAILROAD TRAFFIC) (N.A.B.I.)(AARDOT 851-202W)	10,000.000	DL
900.615	0620	SPECIAL PROVISION (MOBILIZATION/DEMOBILIZATION) (STP BP 15(5))(N.A.B.I.)	43,500.000	DL
900.615	0625	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE) (STP BP 15(5))(N.A.B.I.)	35,000.000	DL
900.620	0630	SPECIAL PROVISION (CAST IRON GRATE WITH FRAME, CONCAVE)	4.000	EACH
900.620	0635	SPECIAL PROVISION (CORING CONCRETE)	3.000	EACH
900.620	0640	SPECIAL PROVISION (CPM SCHEDULE)	10.000	EACH
900.620	0645	SPECIAL PROVISION (JUNCTION BOX, HEAVY DUTY)	21.000	EACH
900.620	0650	SPECIAL PROVISION (LIGHT POLE AND LUMINAIRE)	3.000	EACH
900.620	0655	SPECIAL PROVISION (LIGHT POLE BASE)	22.000	EACH
900.620	0660	SPECIAL PROVISION (MODIFY EXISTING PEDESTRIAN SIGNAL SYSTEM, INTERSECTION)(VT RT 11 @ TH-5)	1.000	EACH
900.620	0665	SPECIAL PROVISION (MODIFY EXISTING PEDESTRIAN SIGNAL SYSTEM, INTERSECTION)(VT RT 11 @ TH-6)	1.000	EACH
900.620	0670	SPECIAL PROVISION (RECTANGULAR RAPID FLASHING BEACON)	4.000	EACH
900.620	0675	SPECIAL PROVISION (REMOVAL AND REPLACEMENT OF CROSS TIES) (10'-0" TIES)	73.000	EACH
900.620	0680	SPECIAL PROVISION (REMOVAL AND REPLACEMENT OF CROSS TIES) (8'-6" TIES)	159.000	EACH
900.620	0685	SPECIAL PROVISION (REMOVAL AND REPLACEMENT OF CROSS TIES) (9'-0" TIES)	20.000	EACH
900.620	0690	SPECIAL PROVISION (SOIL BEARING SLIP BASE)(2 1/2")	4.000	EACH
900.620	0695	SPECIAL PROVISION (VEHICLE STOP BAR DETECTION SYSTEM) (VT ROUTE 11 @ TH-5)	1.000	EACH
900.620	0700	SPECIAL PROVISION (VEHICLE STOP BAR DETECTION SYSTEM) (VT ROUTE 11 @ TH-6)	1.000	EACH
900.640	0705	SPECIAL PROVISION (CONTINUOUS WELDED RAIL)	470.000	LF
900.640	0710	SPECIAL PROVISION (RAISE, ALIGN, AND SURFACE TRACK)	400.000	LF
900.645	0715	SPECIAL PROVISION (PRECAST CONCRETE PANEL GRADE CROSSING SURFACE)(AARDOT 851-202W)	1.000	LS
900.645	0720	SPECIAL PROVISION (RAIL-HIGHWAY CROSSING ACTIVE WARNING SYSTEM)(AARDOT 851-202W)	1.000	LS
900.645	0725	SPECIAL PROVISION (TRAFFIC CONTROL, RAIL-HIGHWAY CROSSING) (AARDOT 851-202W)	1.000	LS
900.650	0730	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)(STP 2970(1))	1.000	LU
900.650	0735	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)(STP BP 15(5))	1.000	LU
900.650	0740	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.) (STP 2970(1))	1.000	LU
900.650	0745	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.) (STP BP 15(5))	1.000	LU
900.670	0750	SPECIAL PROVISION (ASPHALTIC APPROACH MATERIAL)	400.000	SF
900.670	0755	SPECIAL PROVISION (BRICK PAVING)	170.000	SF
900.675	0760	SPECIAL PROVISION (COLD PLANING BITUMINOUS PAVEMENT)	3,200.000	SY
900.675	0765	SPECIAL PROVISION (GREEN PAVEMENT MARKINGS)	150.000	SY
900.675	0770	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	5,620.000	SY
900.680	0775	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	25.000	TON
900.680	0780	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	680.000	TON
900.680	0785	SPECIAL PROVISION (RAILROAD BALLAST)	775.000	TON
402.12 AA1	0790	AGGREGATE SHOULDERS	1,600.000	TON
402.13 AA2	0795	AGGREGATE SHOULDERS, RAP	1,600.000	TON
404.65 BB1	0800	EMULSIFIED ASPHALT	1,226.000	CWT

ITEM NO.	LINE NO.	DESCRIPTION	QUANTITY	UNITS
900.683 BB2	0805	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	1,226.000	CWT

The estimate quantities are not guaranteed but are given as a basis for the comparison of bids.

The right is reserved to reject any or all bids, to waive any formality and any and all technicalities in bids and to accept such bids as may be deemed in the best interest of the awarding agency.

Sincerely,

Maureen Parker

Maureen E. Parker
Administrative Services Manager II