

VERMONT AGENCY OF TRANSPORTATION
SCHEDULE OF ITEMS

PAGE 1
Revised May 15, 2017

LETTING DATE : 05/26/17 11:00 A.M.

CONTRACT ID : 78F329
PROJECT(S) : MORRISTOWN STP HES 030-2(28)
MORRISTOWN BRS 0240(3)S

ITEM NO.	LINE NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001				
201.10	0005	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	1.000	LUMP
203.15	0010	COMMON EXCAVATION	11,820.000	CY
203.16	0015	SOLID ROCK EXCAVATION	180.000	CY
203.27	0020	UNCLASSIFIED CHANNEL EXCAVATION	4,350.000	CY
203.28	0025	EXCAVATION OF SURFACES AND PAVEMENTS	100.000	CY
203.30	0030	EARTH BORROW	2,630.000	CY
203.31	0035	SAND BORROW	3,450.000	CY
203.32	0040	GRANULAR BORROW	1,130.000	CY
204.20	0045	TRENCH EXCAVATION OF EARTH	440.000	CY
204.21	0050	TRENCH EXCAVATION OF ROCK	10.000	CY
204.22	0055	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	2.000	CY
204.25	0060	STRUCTURE EXCAVATION	907.000	CY
204.30	0065	GRANULAR BACKFILL FOR STRUCTURES	1,397.000	CY
205.20	0070	DRILLING AND BLASTING OF SOLID ROCK SUBGRADE	50.000	SY
208.30	0075	COFFERDAM EXCAVATION, EARTH	601.000	CY
208.35	0080	COFFERDAM EXCAVATION, ROCK	27.000	CY
208.40	0085	COFFERDAM (PIER NO. 1)	1.000	LUMP
208.40	0090	COFFERDAM (PIER NO. 2)	1.000	LUMP
210.10	0095	COLD PLANING, BITUMINOUS PAVEMENT	1,440.000	SY
301.35	0100	SUBBASE OF DENSE GRADED CRUSHED STONE	7,130.000	CY
401.10	0105	AGGREGATE SURFACE COURSE	410.000	CY
404.65	0110	EMULSIFIED ASPHALT	52.000	CWT
406.50	0115	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	2.000	LU
490.30	0120	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 70-28)(SBS POLYMER)	1,880.000	TON
490.32	0125	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	2.000	LU
501.33	0130	CONCRETE, HIGH PERFORMANCE CLASS A (FPQ)	235.000	CY
501.34	0135	CONCRETE, HIGH PERFORMANCE CLASS B	444.000	CY
504.10	0140	FURNISHING EQUIPMENT FOR DRIVING PILING	1.000	LUMP
505.20	0145	STEEL PILING, HP 14 X 117	529.000	LF
506.56	0150	STRUCTURAL STEEL, CURVED PLATE GIRDER (FPQ)	441,000.000	LB
507.11	0155	REINFORCING STEEL, LEVEL I	56,957.000	LB
507.13	0160	REINFORCING STEEL, LEVEL III	35,090.000	LB
507.16	0165	DRILLING AND GROUTING DOWELS	114.000	LF
508.15	0170	SHEAR CONNECTORS (2638 - 7/8" X 7")	1.000	LUMP
514.10	0175	WATER REPELLENT, SILANE	40.000	GAL
516.10	0180	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG (FPQ)	30.000	LF
520.10	0187	MEMBRANE WATERPROOFING, SPRAY APPLIED	743.000	SY
524.11	0190	JOINT SEALER, HOT POURED	60.000	LF
525.335	0195	BRIDGE RAILING, GALVANIZED 3 RAIL BOX BEAM (FPQ)	454.000	LF
527.10	0200	MAINTENANCE OF STRUCTURES AND APPROACHES	1.000	LUMP
531.15	0205	BEARING DEVICE ASSEMBLY, HIGH LOAD MULTI-ROTATIONAL	10.000	EACH
540.10	0210	PRECAST CONCRETE STRUCTURE (8'-0" X 6'0" X 64'-0" CATTLE PASS)	1.000	LUMP
541.25	0215	CONCRETE, CLASS B	5.000	CY

VERMONT AGENCY OF TRANSPORTATION
SCHEDULE OF ITEMS

PAGE 2

LETTING DATE : 05/26/17 11:00 A.M.

CONTRACT ID : 78F329
PROJECT(S) : MORRISTOWN STP HES 030-2(28)
MORRISTOWN BRS 0240(3)S

ITEM NO.	LINE NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001				
541.30	0220	CONCRETE, CLASS C	21.000	CY
601.2615	0225	18" CPEP(SL)	174.000	LF
601.2620	0230	24" CPEP(SL)	131.000	LF
601.2625	0235	30" CPEP(SL)	76.000	LF
604.18	0240	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	2.000	EACH
604.21	0245	PRECAST REINFORCED CONCRETE MANHOLE WITH CAST IRON COVER	2.000	EACH
605.10	0250	6 INCH UNDERDRAIN PIPE	350.000	LF
605.20	0255	6 INCH UNDERDRAIN CARRIER PIPE	100.000	LF
605.95	0260	UNDERDRAIN FLUSHING BASIN	2.000	EACH
609.10	0265	DUST CONTROL WITH WATER	30.000	MGAL
613.10	0270	STONE FILL, TYPE I	140.000	CY
613.11	0275	STONE FILL, TYPE II	1,050.000	CY
613.13	0280	STONE FILL, TYPE IV	1,350.000	CY
613.15	0285	RIPRAP, HEAVY TYPE	450.000	CY
617.10	0290	RELOCATE MAILBOX, SINGLE SUPPORT	1.000	EACH
618.11	0295	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	20.000	SY
618.15	0300	BITUMINOUS CONCRETE SIDEWALK	5.000	TON
618.30	0305	DETECTABLE WARNING SURFACE	96.000	SF
619.17	0310	YIELDING MARKER POSTS	16.000	EACH
620.15	0315	GATE FOR CHAIN-LINK FENCE, 4 FEET	15.000	LF
620.55	0320	REMOVAL OF EXISTING FENCE	852.000	LF
621.21	0325	HD STEEL BEAM GUARDRAIL, GALVANIZED	163.000	LF
621.215	0330	HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	322.000	LF
621.217	0335	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	88.000	LF
621.30	0340	BOX BEAM GUARDRAIL	1,390.000	LF
621.51	0345	MANUFACTURED TERMINAL SECTION, TANGENT	8.000	EACH
621.60	0350	ANCHOR FOR STEEL BEAM RAIL	2.000	EACH
621.725	0355	GUARDRAIL APPROACH SECTION, GALVANIZED 3 RAIL BOX BEAM	4.000	EACH
621.80	0360	REMOVAL AND DISPOSAL OF GUARDRAIL	800.000	LF
625.10	0365	SLEEVES FOR UTILITIES (1 X 12")	44.000	LF
625.10	0370	SLEEVES FOR UTILITIES (1 X 18")	52.000	LF
629.54	0375	CRUSHED STONE BEDDING	1.000	TON
630.10	0380	UNIFORMED TRAFFIC OFFICERS	400.000	HR
630.15	0385	FLAGGERS	4,000.000	HR
631.10	0390	FIELD OFFICE, ENGINEERS	1.000	LUMP
631.16	0395	TESTING EQUIPMENT, CONCRETE	1.000	LUMP
631.17	0400	TESTING EQUIPMENT, BITUMINOUS	1.000	LUMP
631.26	0405	FIELD OFFICE TELEPHONE (N.A.B.I.)	4,000.000	DL
634.10	0410	EMPLOYEE TRAINEESHIP	520.000	HR
635.11	0415	MOBILIZATION/DEMOBILIZATION	1.000	LUMP
641.15	0420	PORTABLE CHANGEABLE MESSAGE SIGN	6.000	EACH
646.400	0425	DURABLE 4 INCH WHITE LINE (FPQ)	5,380.000	LF
646.410	0430	DURABLE 4 INCH YELLOW LINE (FPQ)	5,260.000	LF
646.460	0435	DURABLE 12 INCH WHITE LINE (FPQ)	48.000	LF
646.480	0440	DURABLE 24 INCH STOP BAR (FPQ)	33.000	LF

VERMONT AGENCY OF TRANSPORTATION
SCHEDULE OF ITEMS

LETTING DATE : 05/26/17 11:00 A.M.

CONTRACT ID : 78F329
PROJECT(S) : MORRISTOWN STP HES 030-2(28)
MORRISTOWN BRS 0240(3)S

ITEM NO.	LINE NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001				
646.490	0445	DURABLE LETTER OR SYMBOL (FPQ)	4.000	EACH
649.31	0450	GEOTEXTILE UNDER STONE FILL	3,340.000	SY
649.515	0455	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	960.000	SY
649.61	0460	GEOTEXTILE FOR FILTER CURTAIN	250.000	SY
651.15	0465	SEED	270.000	LB
651.18	0470	FERTILIZER	1,120.000	LB
651.20	0475	AGRICULTURAL LIMESTONE	6.000	TON
651.25	0480	HAY MULCH	6.000	TON
651.35	0485	TOPSOIL	1,190.000	CY
651.40	0490	GRUBBING MATERIAL	990.000	SY
652.10	0495	EPSC PLAN (BRS 0240(3)S)	1.000	LUMP
652.10	0500	EPSC PLAN (STP HES 030-2(28))	1.000	LUMP
652.20	0505	MONITORING EPSC PLAN (BRS 0240(3)S)	200.000	HR
652.20	0510	MONITORING EPSC PLAN (STP HES 030-2(28))	200.000	HR
652.30	0515	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BRS 0240(3)S)	1.000	LU
652.30	0520	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (STP HES 030-2(28))	1.000	LU
653.20	0525	TEMPORARY EROSION MATTING	7,450.000	SY
653.25	0530	TEMPORARY STONE CHECK DAM, TYPE I	80.000	CY
653.35	0535	VEHICLE TRACKING PAD	90.000	CY
653.40	0540	INLET PROTECTION DEVICE, TYPE I	2.000	EACH
653.50	0545	BARRIER FENCE	430.000	LF
653.55	0550	PROJECT DEMARCATION FENCE	5,200.000	LF
653.60	0555	EROSION LOG	70.000	LF
675.20	0560	TRAFFIC SIGNS, TYPE A	205.000	SF
675.341	0565	SQUARE TUBE SIGN POST AND ANCHOR	508.000	LF
675.50	0570	REMOVING SIGNS	57.000	EACH
675.60	0575	ERECTING SALVAGED SIGNS	11.000	EACH
676.10	0580	DELINEATOR WITH STEEL POST	18.000	EACH
690.50	0585	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	2.000	LU
900.608	0590	SPECIAL PROVISION (AGGREGATE SURFACE COURSE, TRAIL)	20.000	CY
900.608	0595	SPECIAL PROVISION (GEOGRID - COMPRESSIBLE INCLUSION)	39.000	CY
900.608	0600	SPECIAL PROVISION (RECYCLED ASPHALT SURFACE COURSE)	11.000	CY
900.615	0605	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(N.A.B.I.)	25,000.000	DL
900.620	0610	SPECIAL PROVISION (CPM SCHEDULE)	28.000	EACH
900.640	0615	SPECIAL PROVISION (BRIDGE EXPANSION DEVICE, STRIP SEAL)	31.000	LF
900.640	0620	SPECIAL PROVISION (GUARD AND APPROACH RAIL, PRESSURE TREATED)	420.000	LF
900.640	0625	SPECIAL PROVISION (REINFORCING BAR, GFRP)(#5)	37,700.000	LF
900.640	0630	SPECIAL PROVISION (REINFORCING BAR, GFRP)(#6)	33,400.000	LF
900.640	0635	SPECIAL PROVISION (WOODEN 3-RAIL FENCE)	270.000	LF
900.645	0640	SPECIAL PROVISION (REMOVAL OF TEMPORARY BRIDGE)	1.000	LUMP
900.645	0645	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE) (BRS 0240(3)S)	1.000	LUMP
900.645	0650	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE) (STP HES 030-2(28))	1.000	LUMP
900.650	0655	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, TYPE IVB) (N.A.B.I.)	2.000	LU

VERMONT AGENCY OF TRANSPORTATION
SCHEDULE OF ITEMS

PAGE 4

LETTING DATE : 05/26/17 11:00 A.M.

CONTRACT ID : 78F329
PROJECT(S) : MORRISTOWN STP HES 030-2(28)
MORRISTOWN BRS 0240(3)S

ITEM NO.	LINE NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001				
900.675	0660	SPECIAL PROVISION (HAND PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	390.000	SY
900.680	0665	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, TYPE IVB)(PG 70-28)(SBS POLYMER)	1,250.000	TON