

Revised July 17, 2017

20. NOTICE TO BIDDERS. The Contractor is hereby notified that all signs, supports, mounting frames and posts removed and not reused on the project shall become the property of the Contractor.
21. HIGHWAY PARKING RESTRICTIONS. Only such trucks and equipment as are necessary for the construction of this project will be permitted to stop or park on the shoulders or right-of-way of the highway or intersecting highways. All trucks or equipment so stopped or parked shall be at least 4 feet from the edge of the thru traffic lanes. Parking or stopping on the traveled portion of the roadway will not be permitted unless authorized by the Engineer to meet field conditions.

Private automobiles of workers will not be permitted to stop or park on the shoulders or right-of-way of the highway or intersecting highways.

Each of the Contractor's trucks or equipment used for the construction of this project and permitted to park or stop as provided above shall be equipped with flashing light signals on the front and rear and the signals shall be operating at all times when parked or stopped on the highway unless otherwise authorized by the Engineer.

The flashing light signals shall be visibly distinct from and physically separate from the hazard warning system required by Federal and State motor vehicle laws and regulations. At least one of these flashing light signals shall be visible to traffic approaching from any angle at all times.

Qualified traffic control personnel shall be employed whenever the Contractor's vehicles or equipment (including that which belongs to the individual workers) enter or leave the traffic flow. All movement, in or out of the traffic flow, shall be with the flow of traffic.

22. SPECIAL CONSTRUCTION REQUIREMENTS.

- (a) Unless otherwise permitted in writing by the Engineer, the Contractor shall not work during the holiday periods Memorial Day, July Fourth, Labor Day, Columbus Day, Veterans Day, and Thanksgiving Day. The Engineer shall give a written order designating the time of observance of these holidays and of any additional holidays required by the season, anticipated traffic, and local custom. As specified in Subsection 105.14, construction operations shall not be performed on any Sunday without the specific authorization of the Engineer.

Designated holiday periods shall begin at 12:00 noon on the day before the weekend or holiday, whichever applies, and shall end at 7:00 a.m. on the day after the holiday or the weekend, as appropriate.

- (b) During construction it will be necessary for the Contractor to maintain one-lane traffic for extended periods of time. In no case shall the paved width for this one-lane traffic, including shoulders, be reduced to less than 12 feet. This paved width shall remain free of obstructions and obstacles at all times.

Revised July 17, 2017

(c) Deleted.

(d) Two-way radios shall be provided by the Contractor when requested by the Engineer for use by traffic control personnel. All costs for furnishing and using two-way radios will not be paid for directly, but will be considered incidental to Contract item 635.11, Mobilization/Demobilization.

(e) The Contractor shall have available on the project the current editions of the Manual on Uniform Traffic Control Devices (MUTCD) and the Standard Highway Signs and Markings (SHSM) book.

Information for obtaining these publications may be found at:
<http://mutcd.fhwa.dot.gov/index.htm>.

(f) For this project, the Contractor shall have on hand on the project at all times all necessary materials, equipment, and labor to place any and all necessary interim pavement markings, including temporary line striping targets, required by the Plans or as directed by the Engineer. The markings shall be paid for under the appropriate Contract items.

The costs of maintaining marking capability at all times will not be paid for directly, but will be considered incidental to the pavement marking items in the Contract.

(g) There are special events throughout the year that may require close communication and coordination between the Contractor and the municipality to reduce conflicts. The municipality will advise the Engineer and Contractor of the specifics of each event and the Engineer will direct the Contractor as to what actions, if any, may be necessary on the Contractor's part to minimize impacts to the event.

There will be no extra compensation paid to the Contractor for any inconvenience caused by working around these or other event(s).

SECTION 900 - SPECIAL PROVISION ITEMS

SCHOOL ZONE FLASHING BEACON

23. DESCRIPTION. This work shall consist of installing a school zone flashing beacon at the location(s) indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 678 of the Standard Specifications.

24. GENERAL REQUIREMENTS. Flashing beacons shall meet the requirements and be configured as specified in the plans.

The Contractor shall install beacons where feasible, as determined by the sign manufacturer and the Engineer.