

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
201.10	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	LS	\$20,518.66	176
201.11	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	ACRE	\$33,805.52	9
201.15	REMOVING MEDIUM TREES	EACH	\$1,335.18	7
201.16	REMOVING LARGE TREES	EACH	\$1,500.00	3
201.20	REMOVING MEDIUM STUMPS	EACH	\$199.04	3
201.21	REMOVING LARGE STUMPS	EACH	\$660.92	1
201.30	THINNING AND TRIMMING	ACRE	\$11,670.04	5
201.31	THINNING AND TRIMMING FOR SIGNS	EACH	\$198.62	48
202.10	DEMOLITION AND DISPOSAL OF BUILDING	EACH	\$5,950.00	4
203.15	COMMON EXCAVATION	CY	\$9.86	219
203.16	SOLID ROCK EXCAVATION	CY	\$30.86	87
203.17	UNCLASSIFIED EXCAVATION	CY	\$20.54	23
203.20	MUCK EXCAVATION	CY	\$4.59	1
203.25	CHANNEL EXCAVATION OF EARTH	CY	\$13.59	4
203.26	CHANNEL EXCAVATION OF ROCK	CY	\$140.00	1
203.27	UNCLASSIFIED CHANNEL EXCAVATION	CY	\$13.65	109
203.28	EXCAVATION OF SURFACES AND PAVEMENTS	CY	\$21.94	28
203.30	EARTH BORROW	CY	\$11.33	86
203.31	SAND BORROW	CY	\$19.54	69
203.32	GRANULAR BORROW	CY	\$17.29	27
203.35	GRAVEL BACKFILL FOR SLOPE STABILIZATION	CY	\$36.38	1
203.40	SHOULDER BERM REMOVAL	LF	\$0.38	40
204.20	TRENCH EXCAVATION OF EARTH	CY	\$14.05	115
204.21	TRENCH EXCAVATION OF ROCK	CY	\$148.21	64
204.22	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	CY	\$74.52	305
204.25	STRUCTURE EXCAVATION	CY	\$23.68	119
204.30	GRANULAR BACKFILL FOR STRUCTURES	CY	\$40.30	158
205.10	DRILLING AND BLASTING OF SOLID ROCK	LF	\$28.06	2
205.20	DRILLING AND BLASTING OF SOLID ROCK SUBGRADE	SY	\$13.61	6
208.30	COFFERDAM EXCAVATION, EARTH	CY	\$19.93	28
208.35	COFFERDAM EXCAVATION, ROCK	CY	\$47.75	24
208.40	COFFERDAM	LS	\$154,108.09	37
210.10	COLD PLANING, BITUMINOUS PAVEMENT	SY	\$1.94	210
213.10	MILLED RUMBLE STRIPS	LF	\$0.24	38
301.15	SUBBASE OF GRAVEL	CY	\$25.11	14
301.25	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	CY	\$36.49	21
301.26	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	CY	\$40.03	31

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
301.28	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	TON	\$18.32	51
301.35	SUBBASE OF DENSE GRADED CRUSHED STONE	CY	\$32.09	147
301.40	SUBBASE, RAP	TON	\$16.53	9
310.20	RECLAIMED STABILIZED BASE	SY	\$1.24	18
401.10	AGGREGATE SURFACE COURSE	CY	\$43.60	72
402.12	AGGREGATE SHOULDERS	TON	\$19.15	59
402.13	AGGREGATE SHOULDERS, RAP	TON	\$16.64	44
404.65	EMULSIFIED ASPHALT	CWT	\$25.04	144
406.25	BITUMINOUS CONCRETE PAVEMENT	TON	\$127.86	5
406.27	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT	TON	\$141.65	2
406.28	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	LU	\$1.00	1
406.29	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	LU	\$1.00	1
406.50	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	LU	\$2.88	232
415.25	EMULSIFIED ASPHALT, COLD MIX	CWT	\$29.57	8
417.10	BITUMINOUS CRACK SEALING	LB	\$1.73	7
417.20	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD	LB	\$1.44	23
490.30	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	TON	\$76.66	94
490.31	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	LU	\$1.00	86
490.32	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	LU	\$1.00	64
490.33	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	LU	\$1.00	43
490.34	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	LU	\$1.00	39
501.32	CONCRETE, HIGH PERFORMANCE CLASS AA	CY	\$697.84	2
501.33	CONCRETE, HIGH PERFORMANCE CLASS A	CY	\$857.16	48
501.34	CONCRETE, HIGH PERFORMANCE CLASS B	CY	\$578.58	68
501.35	CONCRETE, HIGH PERFORMANCE CLASS SCC	CY	\$1,310.00	1
502.10	SHORING SUPERSTRUCTURE	LS	\$126,745.10	10
502.11	SHORING SUPERSTRUCTURE BEARINGS	EACH	\$385.89	2
504.10	FURNISHING EQUIPMENT FOR DRIVING PILING	LS	\$68,407.44	57
505.12	STEEL PILING, HP 10 X 57	LF	\$40.69	4
505.15	STEEL PILING, HP 12 X 53	LF	\$30.00	1
505.155	STEEL PILING, HP 12 X 63	LF	\$59.16	14
505.16	STEEL PILING, HP 12 X 74	LF	\$44.83	11
505.165	STEEL PILING, HP 12 X 84	LF	\$66.28	15
505.18	STEEL PILING, HP 14 X 89	LF	\$47.76	9
505.19	STEEL PILING, HP 14 X 102	LF	\$42.61	4
505.20	STEEL PILING, HP 14 X 117	LF	\$63.60	5
505.35	PERMANENT STEEL SHEET PILING	SF	\$32.15	4

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
505.36	TEMPORARY STEEL SHEET PILING	SF	\$15.95	2
505.45	DYNAMIC PILE LOADING TEST	EACH	\$4,562.61	53
506.50	STRUCTURAL STEEL, ROLLED BEAM	LB	\$2.83	9
506.55	STRUCTURAL STEEL, PLATE GIRDER	LB	\$1.82	21
506.56	STRUCTURAL STEEL, CURVED PLATE GIRDER	LB	\$1.84	10
506.60	STRUCTURAL STEEL	LB	\$8.19	19
506.75	STRUCTURAL STEEL	LS	\$62,175.56	9
507.11	REINFORCING STEEL, LEVEL I	LB	\$1.32	109
507.12	REINFORCING STEEL, LEVEL II	LB	\$2.34	46
507.13	REINFORCING STEEL, LEVEL III	LB	\$3.76	14
507.16	DRILLING AND GROUTING DOWELS	LF	\$33.93	43
507.19	MECHANICAL BAR CONNECTOR	EACH	\$37.22	8
508.15	SHEAR CONNECTORS	LS	\$10,390.96	33
509.10	LONGITUDINAL DECK GROOVING	SY	\$14.18	19
510.21	PRESTRESSED CONCRETE BOX BEAMS	LF	\$690.73	2
510.22	PRESTRESSED CONCRETE VOIDED SLABS	LF	\$537.30	4
510.24	GROUTING SHEAR KEYS	LF	\$23.63	11
514.10	WATER REPELLENT, SILANE	GAL	\$70.42	139
516.10	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	LF	\$119.31	140
516.11	BRIDGE EXPANSION JOINT, VERMONT	LF	\$563.06	8
516.12	BRIDGE EXPANSION JOINT, FINGER PLATE	LF	\$1,050.00	1
519.20	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	SY	\$24.90	37
520.10	MEMBRANE WATERPROOFING, SPRAY APPLIED	SY	\$67.40	30
522.20	STRUCTURAL LUMBER AND TIMBER, UNTREATED	MFBM	\$8,776.49	7
522.25	STRUCTURAL LUMBER AND TIMBER, TREATED	MFBM	\$5,686.77	7
522.30	NONSTRUCTURAL LUMBER, UNTREATED	MFBM	\$6,436.84	6
522.40	STRUCTURAL GLUED LAMINATED TIMBER	LS	\$88,155.00	3
524.11	JOINT SEALER, HOT Poured	LF	\$21.60	74
524.21	JOINT SEALER, POLYURETHANE	LF	\$19.37	8
525.10	REMOVAL OF EXISTING BRIDGE RAILING	LF	\$4.63	19
525.11	RESET EXISTING BRIDGE RAILING	LF	\$47.00	1
525.33	BRIDGE RAILING, GALVANIZED 2 RAIL BOX BEAM	LF	\$116.15	19
525.335	BRIDGE RAILING, GALVANIZED 3 RAIL BOX BEAM	LF	\$172.30	25
525.34	BRIDGE RAILING, GALVANIZED 4 RAIL BOX BEAM	LF	\$211.97	3
525.44	BRIDGE RAILING, GALVANIZED HDSB/FASCIA MOUNTED/STEEL TUBING	LF	\$172.50	7
525.45	BRIDGE RAILING, GALVANIZED STEEL TUBING/CONCRETE COMBINATION	LF	\$292.93	11
525.50	BRIDGE RAILING REPAIR, TYPE I	LF	\$15.81	12

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
525.55	BRIDGE RAILING REPAIR, TYPE II	LF	\$27.35	5
525.60	BRIDGE RAILING REPAIR, TYPE III	LF	\$43.24	3
525.70	BRIDGE RAILING, CONCRETE F-SHAPE	LF	\$311.52	2
527.10	MAINTENANCE OF STRUCTURES AND APPROACHES	LS	\$6,474.47	17
528.10	ONE-WAY TEMPORARY BRIDGE	LS	\$188,750.00	4
528.11	TWO-WAY TEMPORARY BRIDGE	LS	\$262,266.67	15
529.10	REMOVAL OF BRIDGE PAVEMENT	SY	\$24.58	17
529.15	REMOVAL OF STRUCTURE	EACH	\$77,273.01	83
529.20	PARTIAL REMOVAL OF STRUCTURE	EACH	\$96,734.05	38
529.25	REMOVAL OF CONCRETE OR MASONRY	CY	\$280.76	13
531.15	BEARING DEVICE ASSEMBLY, HIGH LOAD MULTI-ROTATIONAL	EACH	\$3,124.37	5
531.16	BEARING DEVICE ASSEMBLY, PLAIN ELASTOMERIC PAD	EACH	\$634.31	13
531.17	BEARING DEVICE ASSEMBLY, STEEL REINFORCED ELASTOMERIC PAD	EACH	\$678.88	46
531.18	BEARING DEVICE ASSEMBLY, ELASTOMERIC PAD W/ EXT. LOAD PLATES	EACH	\$2,719.59	7
531.19	REMOVE AND REPLACE EXISTING ANCHOR BOLT	EACH	\$179.20	2
540.10	PRECAST CONCRETE STRUCTURE	LS	\$278,453.88	81
541.22	CONCRETE, CLASS A	CY	\$1,093.90	3
541.25	CONCRETE, CLASS B	CY	\$821.48	33
541.30	CONCRETE, CLASS C	CY	\$308.40	19
541.31	CONCRETE, CLASS D	CY	\$275.45	3
541.45	CONTROLLED DENSITY (FLOWABLE) FILL	CY	\$214.75	24
545.20	PREFABRICATED MULTI-MODAL BRIDGE	LS	\$452,000.00	1
580.10	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	SY	\$127.54	10
580.11	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	SY	\$244.49	10
580.12	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	CY	\$898.48	10
580.13	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS I	SY	\$480.38	12
580.14	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS II	SY	\$857.87	15
580.15	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS III	CY	\$2,438.66	8
580.16	SURFACE PREPARATION FOR MEMBRANE	SF	\$0.41	10
580.17	RAPID SETTING CONCRETE REPAIR MATERIAL	CF	\$175.00	2
580.20	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	CF	\$129.08	64
580.21	POLYMER CONCRETE REPAIR MATERIAL	CY	\$12,000.00	2
601.0005	12" CSP .064 (2-2/3 X 1/2)	LF	\$58.61	6
601.0010	15" CSP .064 (2-2/3 X 1/2)	LF	\$69.35	4
601.0011	15" CSP .079 (2-2/3 X 1/2)	LF	\$99.03	3
601.0015	18" CSP .064 (2-2/3 X 1/2)	LF	\$105.87	8
601.0016	18" CSP .079 (2-2/3 X 1/2)	LF	\$74.75	3

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
601.0025	24" CSP .064 (2-2/3 X 1/2)	LF	\$88.94	5
601.0036	30" CSP .079 (2-2/3 X 1/2)	LF	\$148.13	2
601.0046	36" CSP .079 (2-2/3 X 1/2)	LF	\$284.89	2
601.0215	18" CAAP .060 (2-2/3 X 1/2)	LF	\$80.00	1
601.0252	42" CAAP .105 (2-2/3 X 1/2)	LF	\$125.00	1
601.0405	12" PCCSP .064 (2-2/3 X 1/2)	LF	\$87.45	1
601.0410	15" PCCSP .064 (2-2/3 X 1/2)	LF	\$135.00	1
601.0415	18" PCCSP .064 (2-2/3 X 1/2)	LF	\$125.70	7
601.0416	18" PCCSP .079 (2-2/3 X 1/2)	LF	\$40.00	1
601.0425	24" PCCSP .064 (2-2/3 X 1/2)	LF	\$126.41	6
601.0436	30" PCCSP .079 (2-2/3 X 1/2)	LF	\$64.36	2
601.0446	36" PCCSP .079 (2-2/3 X 1/2)	LF	\$76.81	1
601.0452	42" PCCSP .109 (2-2/3 X 1/2)	LF	\$120.00	1
601.0457	48" PCCSP .109 (2-2/3 X 1/2)	LF	\$110.57	2
601.0526	54" PCCSP .079 (3 X 1)	LF	\$85.85	1
601.0542	72" PCCSP .109 (3 X 1)	LF	\$300.00	1
601.0615	18" PCCSP(PI) .064 (2-2/3 X 1/2)	LF	\$300.00	1
601.0657	48" PCCSP(PI) .109 (2-2/3 X 1/2)	LF	\$267.00	2
601.0805	12" RCP CLASS III	LF	\$301.83	1
601.0810	15" RCP CLASS III	LF	\$124.00	1
601.0811	15" RCP CLASS IV	LF	\$273.33	2
601.0815	18" RCP CLASS III	LF	\$68.31	12
601.0816	18" RCP CLASS IV	LF	\$53.88	2
601.0817	18" RCP CLASS V	LF	\$106.44	4
601.0825	24" RCP CLASS III	LF	\$325.00	1
601.0827	24" RCP CLASS V	LF	\$91.00	1
601.0845	36" RCP CLASS III	LF	\$225.00	1
601.0855	48" RCP CLASS III	LF	\$97.54	1
601.0866	60" RCP CLASS IV	LF	\$256.47	1
601.0905	12" CPEP	LF	\$39.24	5
601.0910	15" CPEP	LF	\$34.05	6
601.0915	18" CPEP	LF	\$64.04	24
601.0920	24" CPEP	LF	\$61.37	8
601.2605	12" CPEP(SL)	LF	\$42.65	5
601.2610	15" CPEP(SL)	LF	\$40.44	13
601.2615	18" CPEP(SL)	LF	\$44.99	50
601.2620	24" CPEP(SL)	LF	\$66.15	22

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
601.2625	30" CPEP(SL)	LF	\$47.78	10
601.2630	36" CPEP(SL)	LF	\$58.11	5
601.2635	42" CPEP(SL)	LF	\$116.17	2
601.2640	48" CPEP(SL)	LF	\$69.31	1
601.2650	60" CPEP(SL)	LF	\$111.08	1
601.2815	18" CPPP(SL)	LF	\$45.00	1
601.3457	57 IN. X 38 IN. PCCSPA .109 (2-2/3X1/2)	LF	\$166.94	2
601.5415	18" PCCSP ELBOW .064 (2-2/3 X 1/2)	EACH	\$340.00	1
601.5456	42" PCCSP ELBOW .109 (2-2/3 X 1/2)	EACH	\$1,000.00	1
601.5814	18" CPEP ELBOW	EACH	\$200.00	1
601.6010	15" CSPES .064 (2-2/3 X 1/2)	EACH	\$164.00	1
601.6015	18" CSPES .064 (2-2/3 X 1/2)	EACH	\$290.67	5
601.6025	24" CSPES .064 (2-2/3 X 1/2)	EACH	\$651.00	1
601.6036	30" CSPES .079 (2-2/3 X 1/2)	EACH	\$468.00	1
601.6046	36" CSPES .079 (2-2/3 X 1/2)	EACH	\$600.00	1
601.6057	48" CSPES .109 (2-2/3 X 1/2)	EACH	\$1,300.00	1
601.6815	18" RCPES CLASS III	EACH	\$895.67	3
601.6845	36" RCPES CLASS III	EACH	\$2,100.00	1
601.7005	12" CPEPES	EACH	\$413.55	3
601.7010	15" CPEPES	EACH	\$321.80	5
601.7015	18" CPEPES	EACH	\$379.11	20
601.7020	24" CPEPES	EACH	\$518.83	5
601.7025	30" CPEPES	EACH	\$700.00	1
601.99	RE-LAYING PIPE CULVERTS	LF	\$48.19	2
601.995	CLEANING CULV. PIPE, IN-PLACE [0 TO 24 IN., INCL.]	LF	\$24.68	16
601.996	CLEANING CULV. PIPE, IN-PLACE [GREATER THAN 24 IN.]	LF	\$35.22	9
602.20	DRY MASONRY	CY	\$597.49	4
602.30	REPOINTING MASONRY	SY	\$280.61	2
602.35	REBUILT STONE MASONRY	CY	\$811.58	12
602.40	REPAIRING STONE MASONRY	SY	\$411.32	5
604.10	CONCRETE CATCH BASIN WITH CAST IRON GRATE	EACH	\$2,678.00	1
604.18	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	EACH	\$4,009.29	41
604.20	PRECAST REINFORCED CONCRETE CATCH BASIN WITH CAST IRON GRATE	EACH	\$3,387.59	23
604.21	PRECAST REINFORCED CONCRETE MANHOLE WITH CAST IRON COVER	EACH	\$9,652.51	13
604.22	SANITARY SEWER MANHOLE	EACH	\$3,133.21	3
604.25	PRECAST REINFORCED CONCRETE PIPE DI WITH CAST IRON GRATE	EACH	\$3,553.33	2
604.30	PRECAST REINFORCED CONCRETE CURB DI WITH CAST IRON GRATE	EACH	\$4,082.75	1

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
604.40	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	EACH	\$736.97	30
604.412	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	EACH	\$1,155.94	55
604.415	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	EACH	\$1,130.57	38
604.418	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	EACH	\$1,087.53	17
604.42	CHANGING ELEVATION OF SEWER MANHOLES	EACH	\$763.42	43
604.46	CAST IRON GRATE WITH FRAME, TYPE B	EACH	\$826.00	2
604.47	CAST IRON GRATE WITH FRAME, TYPE D	EACH	\$753.02	4
604.55	CAST IRON COVER WITH FRAME	EACH	\$762.78	6
604.56	CAST IRON COVER WITH FRAME, SEWER	EACH	\$883.21	3
605.10	6 INCH UNDERDRAIN PIPE	LF	\$21.86	43
605.11	8 INCH UNDERDRAIN PIPE	LF	\$27.04	11
605.13	12 INCH UNDERDRAIN PIPE	LF	\$47.00	1
605.20	6 INCH UNDERDRAIN CARRIER PIPE	LF	\$24.43	23
605.21	8 INCH UNDERDRAIN CARRIER PIPE	LF	\$24.18	8
605.23	12 INCH UNDERDRAIN CARRIER PIPE	LF	\$58.02	2
605.95	UNDERDRAIN FLUSHING BASIN	EACH	\$359.78	26
607.10	ROADWAY PATROL MAINTENANCE	HR	\$138.48	4
608.10	BULLDOZER RENTAL, TYPE I	HR	\$77.68	7
608.15	POWER GRADER RENTAL	HR	\$59.30	69
608.25	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	HR	\$81.71	109
608.26	ALL PURPOSE EXCAVATOR RENTAL, TYPE II	HR	\$187.45	8
608.30	POWER BROOM RENTAL, TYPE I	HR	\$26.94	94
608.31	POWER BROOM RENTAL, TYPE II	HR	\$69.37	61
608.37	TRUCK RENTAL	HR	\$67.54	110
608.40	LOADER RENTAL, TYPE I	HR	\$41.88	75
608.45	TRUCK-MOUNTED ATTENUATOR	HR	\$15.63	18
608.50	TRUCK-MOUNTED ATTENUATOR, AWV/PV	HR	\$11.69	23
609.10	DUST CONTROL WITH WATER	MGAL	\$20.84	92
609.15	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	TON	\$738.25	40
613.10	STONE FILL, TYPE I	CY	\$43.91	115
613.11	STONE FILL, TYPE II	CY	\$42.49	94
613.12	STONE FILL, TYPE III	CY	\$45.26	61
613.13	STONE FILL, TYPE IV	CY	\$43.32	55
613.15	RIPRAP, HEAVY TYPE	CY	\$42.67	7
613.16	RIPRAP, LIGHT TYPE	CY	\$49.09	2
613.25	GABION WALL	CY	\$188.55	2
616.20	GRANITE SLOPE EDGING	LF	\$42.35	9

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
616.21	VERTICAL GRANITE CURB	LF	\$35.69	38
616.22	GRANITE BRIDGE CURB	LF	\$66.00	1
616.225	REPOINTING GRANITE BRIDGE CURB	GAL	\$64.90	7
616.25	PRECAST REINFORCED CONCRETE CURB, TYPE A	LF	\$50.00	1
616.26	PRECAST REINFORCED CONCRETE CURB, TYPE B	LF	\$36.50	8
616.28	CAST-IN-PLACE CONCRETE CURB, TYPE B	LF	\$31.18	44
616.305	BITUMINOUS CONCRETE CURB, TYPE A	LF	\$6.22	13
616.35	TREATED TIMBER CURB	LF	\$12.80	13
616.40	REMOVING AND RESETTING CURB	LF	\$21.39	19
616.41	REMOVAL OF EXISTING CURB	LF	\$4.54	43
616.47	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	TON	\$207.06	24
617.10	RELOCATE MAILBOX, SINGLE SUPPORT	EACH	\$154.03	61
617.12	RELOCATE MAILBOX, MULTIPLE SUPPORT	EACH	\$224.06	24
618.10	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SY	\$68.33	56
618.11	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	SY	\$78.68	16
618.15	BITUMINOUS CONCRETE SIDEWALK	TON	\$135.59	7
618.30	DETECTABLE WARNING SURFACE	SF	\$45.96	52
619.10	BOUNDARY MARKERS	EACH	\$1,350.00	1
619.14	BOLLARDS	EACH	\$341.09	6
619.15	WOOD MARKER POSTS	EACH	\$284.27	3
619.16	STEEL MARKER POSTS	EACH	\$46.20	11
619.17	YIELDING MARKER POSTS	EACH	\$32.30	88
619.20	REMOVING AND RESETTING PROPERTY MARKERS	EACH	\$262.50	5
620.11	CHAIN-LINK FENCE, 4 FEET	LF	\$30.81	6
620.12	CHAIN-LINK FENCE, 6 FEET	LF	\$19.24	8
620.15	GATE FOR CHAIN-LINK FENCE, 4 FEET	LF	\$130.00	1
620.16	GATE FOR CHAIN-LINK FENCE, 6 FEET	LF	\$65.97	4
620.20	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 4 FEET	EACH	\$107.86	4
620.21	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 6 FEET	EACH	\$158.26	5
620.22	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 8 FEET	EACH	\$172.50	1
620.25	WOVEN WIRE FENCE WITH STEEL POSTS	LF	\$9.41	5
620.26	WOVEN WIRE FENCE WITH WOOD POSTS	LF	\$12.20	4
620.30	DRIVE GATE FOR WOVEN WIRE FENCE	EACH	\$920.00	2
620.40	STEEL BRACE FOR WOVEN WIRE FENCE	EACH	\$214.83	4
620.41	WOOD BRACE FOR WOVEN WIRE FENCE	EACH	\$106.70	2
620.50	REMOVING AND RESETTING FENCE	LF	\$8.71	28
620.55	REMOVAL OF EXISTING FENCE	LF	\$3.89	28

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
620.75	SNOW BARRIER	LF	\$46.75	5
621.15	PLANK RAIL	LF	\$51.99	3
621.17	CABLE GUARDRAIL	LF	\$7.25	2
621.173	CABLE GUARDRAIL J-BOLT, GALVANIZED	EACH	\$1.00	2
621.174	CABLE GUARDRAIL SPLICE UNIT	EACH	\$59.18	2
621.175	REPLACEMENT OF GUARDRAIL CABLE	LF	\$2.17	2
621.18	STEEL BACKED TIMBER GUARDRAIL	LF	\$133.11	4
621.20	STEEL BEAM GUARDRAIL, GALVANIZED	LF	\$15.93	121
621.205	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	LF	\$17.46	52
621.206	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	LF	\$23.59	18
621.207	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	LF	\$25.34	12
621.21	HD STEEL BEAM GUARDRAIL, GALVANIZED	LF	\$21.21	42
621.215	HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	LF	\$22.55	16
621.216	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	LF	\$25.04	14
621.217	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	LF	\$30.93	11
621.218	STEEL BEAM GUARDRAIL DELINEATOR	EACH	\$5.86	7
621.219	STEEL BEAM GUARDRAIL OFFSET BLOCK	EACH	\$50.00	1
621.30	BOX BEAM GUARDRAIL	LF	\$45.45	39
621.45	CONCRETE MEDIAN BARRIER	LF	\$110.00	1
621.50	MANUFACTURED TERMINAL SECTION, FLARED	EACH	\$1,767.35	36
621.51	MANUFACTURED TERMINAL SECTION, TANGENT	EACH	\$3,123.78	40
621.53	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	EACH	\$848.36	9
621.56	ENERGY ABSORPTION ATTENUATOR	EACH	\$1,921.23	20
621.57	ENERGY ABSORPTION ATTENUATOR, SAND-FILLED PLASTIC BARREL	EACH	\$1,000.00	1
621.60	ANCHOR FOR STEEL BEAM RAIL	EACH	\$710.08	127
621.61	ANCHOR FOR STEEL TO BOX BEAM TRANSITION	EACH	\$1,950.00	1
621.65	ANCHOR FOR CABLE RAIL	EACH	\$1,415.69	2
621.70	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE I	EACH	\$1,405.85	6
621.71	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE II	EACH	\$892.72	4
621.72	GUARDRAIL APPROACH SECTION, GALVANIZED 2 RAIL BOX BEAM	EACH	\$5,586.92	26
621.725	GUARDRAIL APPROACH SECTION, GALVANIZED 3 RAIL BOX BEAM	EACH	\$5,758.74	23
621.73	GUARDRAIL APPROACH SECTION, GALVANIZED 4 RAIL BOX BEAM	EACH	\$8,253.20	3
621.735	GUARDRAIL APPROACH SECTION, STEEL BEAM	EACH	\$189.00	1
621.737	GUARDRAIL APPROACH SECTION, GALV HD STEEL BEAM	EACH	\$1,183.87	13
621.738	GUARDRAIL APPROACH SECTION, GALV HD STEEL BEAM W/ 8FT POSTS	EACH	\$1,226.35	5
621.746	GUARDRAIL APPROACH SECTION TO CONCRETE BRIDGE RAILING, TL-2	EACH	\$1,100.00	2
621.747	GUARDRAIL APPROACH SECTION TO CONCRETE BRIDGE RAILING, TL-3	EACH	\$2,140.00	4

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
621.748	GUARDRAIL APPROACH SECTION, CONC COMB BRIDGE RAILING TL-3	EACH	\$1,862.50	2
621.75	REMOVE AND RESET GUARDRAIL	LF	\$6.51	49
621.76	REPLACE GUARDRAIL POST ASSEMBLY	EACH	\$34.65	21
621.77	REPLACE GUARDRAIL BEAM UNIT	EACH	\$102.69	24
621.79	ADJUST HEIGHT OF GUARDRAIL	LF	\$4.20	11
621.80	REMOVAL AND DISPOSAL OF GUARDRAIL	LF	\$0.90	178
621.81	REMOVAL AND DISPOSAL OF GUIDE POSTS	EACH	\$6.78	11
621.85	GUIDE POSTS	EACH	\$50.38	4
621.90	TEMPORARY TRAFFIC BARRIER	LF	\$12.90	52
621.95	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	LF	\$8.95	21
622.10	INSULATION BOARD	MFBM	\$1,194.88	7
625.10	SLEEVES FOR UTILITIES	LF	\$92.26	7
628.28	DUCTILE IRON PIPE, CEMENT-LINED	LF	\$72.61	2
628.35	PVC SEWER PIPE	LF	\$36.13	2
628.42	TRANSFER TO NEW SYSTEM, SANITARY SEWER	LS	\$8,800.00	5
629.20	ADJUST ELEVATION OF VALVE BOX	EACH	\$175.46	36
629.23	SEAMLESS COPPER WATER TUBE	LF	\$27.29	3
629.24	DUCTILE IRON PIPE, CEMENT-LINED	LF	\$75.48	6
629.25	EXTENSION SERVICE BOX AND CURB STOP	EACH	\$506.75	5
629.26	GATE VALVE	EACH	\$1,355.55	2
629.27	GATE VALVE WITH VALVE BOX	EACH	\$1,943.57	4
629.28	HYDRANT	EACH	\$3,741.25	3
629.29	RELOCATE HYDRANT	EACH	\$3,223.34	3
629.30	REMOVE HYDRANT	EACH	\$1,151.22	4
629.32	PLASTIC WATER PIPE, FLEXIBLE	LF	\$12.36	2
629.33	PLASTIC WATER PIPE, RIGID	LF	\$101.09	1
629.35	TAPPING SLEEVE AND VALVE WITH VALVE BOX	EACH	\$3,676.52	1
629.39	CORPORATION STOP	EACH	\$492.51	3
629.40	EXPANSION ASSEMBLY	EACH	\$2,951.21	1
629.42	TRANSFER TO NEW SYSTEM, WATER SYSTEM	LS	\$12,540.92	10
629.44	PIPE INSULATION	LF	\$6.71	1
629.54	CRUSHED STONE BEDDING	TON	\$34.04	15
630.10	UNIFORMED TRAFFIC OFFICERS	HR	\$52.06	260
630.15	FLAGGERS	HR	\$23.78	299
630.20	FLAGGERS, RAILROAD	HR	\$101.67	4
631.10	FIELD OFFICE, ENGINEERS	LS	\$17,384.42	233
631.11	FIELD OFFICE, SOILS AND MATERIALS	LS	\$28,146.62	3

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
631.12	COMBINED ENGINEERS AND SOILS OFFICE	LS	\$482.81	1
631.16	TESTING EQUIPMENT, CONCRETE	LS	\$913.48	170
631.17	TESTING EQUIPMENT, BITUMINOUS	LS	\$782.34	210
631.18	TESTING EQUIPMENT, PROTECTIVE COATINGS	LS	\$2,450.33	10
631.26	FIELD OFFICE TELEPHONE (N.A.B.I.)	DL	\$1.00	232
634.10	EMPLOYEE TRAINEESHIP	HR	\$13.37	86
635.11	MOBILIZATION/DEMOBILIZATION	LS	\$166,936.10	341
641.10	TRAFFIC CONTROL	LS	\$118,817.87	239
641.12	PUBLIC RELATIONS OFFICER	LS	\$8,175.56	9
641.15	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	\$3,478.44	190
641.16	PORTABLE ARROW BOARD	EACH	\$1,903.96	17
641.17	PORTABLE CHANGEABLE MESSAGE SIGN RENTAL	DAY	\$30.59	14
646.20	4 INCH WHITE LINE	LF	\$0.44	66
646.201	4 INCH WHITE LINE, WATERBORNE PAINT	LF	\$0.06	18
646.202	4 INCH WHITE LINE, LOW VOC CHLORINATED RUBBER PAINT	LF	\$0.20	1
646.21	4 INCH YELLOW LINE	LF	\$0.06	78
646.2111	4 INCH YELLOW LINE, WATERBORNE PAINT	LF	\$0.06	22
646.2112	4 INCH YELLOW LINE, LOW VOC CHLORINATED RUBBER PAINT	LF	\$0.20	1
646.214	6 INCH WHITE LINE	LF	\$0.10	10
646.2141	6 INCH WHITE LINE, WATERBORNE PAINT	LF	\$0.08	10
646.2142	6 INCH WHITE LINE, LOW VOC CHLORINATED RUBBER PAINT	LF	\$0.25	1
646.215	6 INCH YELLOW LINE	LF	\$0.09	6
646.2151	6 INCH YELLOW LINE, WATERBORNE PAINT	LF	\$0.08	10
646.22	8 INCH WHITE LINE	LF	\$2.10	1
646.221	8 INCH WHITE LINE, WATERBORNE PAINT	LF	\$0.23	7
646.222	8 INCH WHITE LINE, LOW VOC CHLORINATED RUBBER PAINT	LF	\$1.25	1
646.23	8 INCH YELLOW LINE	LF	\$3.00	1
646.231	8 INCH YELLOW LINE, WATERBORNE PAINT	LF	\$0.18	4
646.232	8 INCH YELLOW LINE, LOW VOC CHLORINATED RUBBER PAINT	LF	\$1.25	1
646.24	12 INCH WHITE LINE	LF	\$0.38	4
646.241	12 INCH WHITE LINE, WATERBORNE PAINT	LF	\$0.29	8
646.25	12 INCH YELLOW LINE	LF	\$1.00	1
646.251	12 INCH YELLOW LINE, WATERBORNE PAINT	LF	\$0.38	3
646.26	24 INCH STOP BAR	LF	\$1.80	26
646.261	24 INCH STOP BAR, WATERBORNE PAINT	LF	\$1.53	9
646.262	24 INCH STOP BAR, LOW VOC CHLORINATED RUBBER PAINT	LF	\$3.00	1
646.30	LETTER OR SYMBOL	EACH	\$21.97	24

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
646.301	LETTER OR SYMBOL, WATERBORNE PAINT	EACH	\$15.72	9
646.302	LETTER OR SYMBOL, LOW VOC CHLORINATED RUBBER PAINT	EACH	\$38.00	1
646.31	CROSSWALK MARKING	LF	\$5.12	5
646.311	CROSSWALK MARKING, WATERBORNE PAINT	LF	\$5.77	5
646.312	CROSSWALK MARKING, LOW VOC CHLORINATED RUBBER PAINT	LF	\$6.50	1
646.32	RAILROAD CROSSING SYMBOL	EACH	\$317.62	5
646.321	RAILROAD CROSSING SYMBOL, WATERBORNE PAINT	EACH	\$306.27	5
646.322	RAILROAD CROSSING SYMBOL, LOW VOC CHLORINATED RUBBER PAINT	EACH	\$400.00	1
646.400	DURABLE 4 INCH WHITE LINE	LF	\$1.38	18
646.4011	DURABLE 4 INCH WHITE LINE, TYPE A TAPE	LF	\$2.25	7
646.402	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	LF	\$3.77	12
646.403	DURABLE 4 INCH WHITE LINE, EPOXY PAINT	LF	\$0.41	5
646.404	DURABLE 4 INCH WHITE LINE, POLYUREA	LF	\$0.48	57
646.406	DURABLE 4 INCH WHITE LINE, RECESSED POLYUREA	LF	\$1.37	10
646.4071	DURABLE 4 INCH WHITE LINE, RECESSED TYPE A TAPE	LF	\$3.25	1
646.408	DURABLE 4 INCH WHITE LINE, RECESSED THERMOPLASTIC	LF	\$3.20	1
646.410	DURABLE 4 INCH YELLOW LINE	LF	\$1.46	22
646.4111	DURABLE 4 INCH YELLOW LINE, TYPE A TAPE	LF	\$2.27	7
646.412	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	LF	\$3.06	12
646.413	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	LF	\$0.38	6
646.414	DURABLE 4 INCH YELLOW LINE, POLYUREA	LF	\$0.48	57
646.416	DURABLE 4 INCH YELLOW LINE, RECESSED POLYUREA	LF	\$1.24	10
646.4171	DURABLE 4 INCH YELLOW LINE, RECESSED TYPE A TAPE	LF	\$3.25	1
646.418	DURABLE 4 INCH YELLOW LINE, RECESSED THERMOPLASTIC	LF	\$3.10	1
646.420	DURABLE 6 INCH WHITE LINE	LF	\$0.50	1
646.4211	DURABLE 6 INCH WHITE LINE, TYPE A TAPE	LF	\$3.18	4
646.422	DURABLE 6 INCH WHITE LINE, THERMOPLASTIC	LF	\$0.83	3
646.424	DURABLE 6 INCH WHITE LINE, POLYUREA	LF	\$0.59	15
646.426	DURABLE 6 INCH WHITE LINE, RECESSED POLYUREA	LF	\$0.81	4
646.4271	DURABLE 6 INCH WHITE LINE, RECESSED TYPE A TAPE	LF	\$4.25	1
646.430	DURABLE 6 INCH YELLOW LINE	LF	\$3.44	2
646.4311	DURABLE 6 INCH YELLOW LINE, TYPE A TAPE	LF	\$3.13	2
646.432	DURABLE 6 INCH YELLOW LINE, THERMOPLASTIC	LF	\$1.22	4
646.434	DURABLE 6 INCH YELLOW LINE, POLYUREA	LF	\$0.59	15
646.436	DURABLE 6 INCH YELLOW LINE, RECESSED POLYUREA	LF	\$0.80	3
646.4371	DURABLE 6 INCH YELLOW LINE, RECESSED TYPE A TAPE	LF	\$4.25	1
646.440	DURABLE 8 INCH WHITE LINE	LF	\$1.20	1

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
646.4411	DURABLE 8 INCH WHITE LINE, TYPE A TAPE	LF	\$4.34	7
646.442	DURABLE 8 INCH WHITE LINE, THERMOPLASTIC	LF	\$1.33	8
646.443	DURABLE 8 INCH WHITE LINE, EPOXY PAINT	LF	\$3.00	1
646.444	DURABLE 8 INCH WHITE LINE, POLYUREA	LF	\$1.99	8
646.446	DURABLE 8 INCH WHITE LINE, RECESSED POLYUREA	LF	\$3.41	3
646.450	DURABLE 8 INCH YELLOW LINE	LF	\$1.20	1
646.4511	DURABLE 8 INCH YELLOW LINE, TYPE A TAPE	LF	\$4.31	6
646.452	DURABLE 8 INCH YELLOW LINE, THERMOPLASTIC	LF	\$1.40	7
646.453	DURABLE 8 INCH YELLOW LINE, EPOXY PAINT	LF	\$3.00	1
646.454	DURABLE 8 INCH YELLOW LINE, POLYUREA	LF	\$1.74	15
646.456	DURABLE 8 INCH YELLOW LINE, RECESSED POLYUREA	LF	\$3.08	6
646.4571	DURABLE 8 INCH YELLOW LINE, RECESSED TYPE A TAPE	LF	\$9.00	1
646.460	DURABLE 12 INCH WHITE LINE	LF	\$3.96	5
646.4611	DURABLE 12 INCH WHITE LINE, TYPE A TAPE	LF	\$6.26	1
646.462	DURABLE 12 INCH WHITE LINE, THERMOPLASTIC	LF	\$8.31	2
646.463	DURABLE 12 INCH WHITE LINE, EPOXY PAINT	LF	\$23.50	2
646.464	DURABLE 12 INCH WHITE LINE, POLYUREA	LF	\$1.30	12
646.466	DURABLE 12 INCH WHITE LINE, RECESSED POLYUREA	LF	\$2.54	5
646.4671	DURABLE 12 INCH WHITE LINE, RECESSED TYPE A TAPE	LF	\$11.00	1
646.474	DURABLE 12 INCH YELLOW LINE, POLYUREA	LF	\$2.26	4
646.480	DURABLE 24 INCH STOP BAR	LF	\$11.68	21
646.481	DURABLE 24 INCH STOP BAR, TYPE I TAPE	LF	\$7.06	3
646.4811	DURABLE 24 INCH STOP BAR, TYPE A TAPE	LF	\$10.96	7
646.482	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	LF	\$4.11	23
646.483	DURABLE 24 INCH STOP BAR, EPOXY PAINT	LF	\$9.34	4
646.484	DURABLE 24 INCH STOP BAR, POLYUREA	LF	\$5.18	37
646.486	DURABLE 24 INCH STOP BAR, RECESSED POLYUREA	LF	\$16.95	5
646.487	DURABLE 24 INCH STOP BAR, RECESSED TYPE I TAPE	LF	\$10.98	2
646.4871	DURABLE 24 INCH STOP BAR, RECESSED TYPE A TAPE	LF	\$16.92	2
646.4873	DURABLE 24 INCH STOP BAR, RECESSED TYPE C TAPE	LF	\$30.00	1
646.490	DURABLE LETTER OR SYMBOL	EACH	\$85.27	13
646.4911	DURABLE LETTER OR SYMBOL, TYPE A TAPE	EACH	\$130.51	2
646.4913	DURABLE LETTER OR SYMBOL, TYPE C TAPE	EACH	\$200.00	1
646.4914	DURABLE LETTER OR SYMBOL, TYPE D TAPE	EACH	\$110.11	6
646.492	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	EACH	\$49.21	25
646.493	DURABLE LETTER OR SYMBOL, EPOXY PAINT	EACH	\$83.60	5
646.494	DURABLE LETTER OR SYMBOL, POLYUREA	EACH	\$64.24	40

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
646.496	DURABLE LETTER OR SYMBOL, RECESSED POLYUREA	EACH	\$453.67	3
646.4971	DURABLE LETTER OR SYMBOL, RECESSED TYPE A TAPE	EACH	\$400.00	1
646.4973	DURABLE LETTER OR SYMBOL, RECESSED TYPE C TAPE	EACH	\$375.00	1
646.500	DURABLE CROSSWALK MARKING	LF	\$14.37	4
646.501	DURABLE CROSSWALK MARKING, TYPE I TAPE	LF	\$17.81	2
646.5011	DURABLE CROSSWALK MARKING, TYPE A TAPE	LF	\$18.49	7
646.502	DURABLE CROSSWALK MARKING, THERMOPLASTIC	LF	\$9.75	13
646.504	DURABLE CROSSWALK MARKING, POLYUREA	LF	\$12.31	9
646.506	DURABLE CROSSWALK MARKING, RECESSED POLYUREA	LF	\$43.07	2
646.5073	DURABLE CROSSWALK MARKING, RECESSED TYPE C TAPE	LF	\$50.00	1
646.510	DURABLE RAILROAD CROSSING SYMBOL	EACH	\$595.83	5
646.511	DURABLE RAILROAD CROSSING SYMBOL, TYPE I TAPE	EACH	\$818.37	2
646.5111	DURABLE RAILROAD CROSSING SYMBOL, TYPE A TAPE	EACH	\$561.22	3
646.5114	DURABLE RAILROAD CROSSING SYMBOL, TYPE D TAPE	EACH	\$576.92	4
646.512	DURABLE RAILROAD CROSSING SYMBOL, THERMOPLASTIC	EACH	\$468.93	6
646.513	DURABLE RAILROAD CROSSING SYMBOL, EPOXY PAINT	EACH	\$1,200.00	1
646.514	DURABLE RAILROAD CROSSING SYMBOL, POLYUREA	EACH	\$513.27	5
646.600	TEMPORARY 4 INCH WHITE LINE	LF	\$0.14	20
646.6011	TEMPORARY 4 INCH WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	LF	\$1.41	7
646.602	TEMPORARY 4 INCH WHITE LINE, PAINT	LF	\$0.08	73
646.610	TEMPORARY 4 INCH YELLOW LINE	LF	\$0.16	21
646.6111	TEMPORARY 4 IN YELLOW LINE, TEMPORARY PAVEMENT MARKING TAPE	LF	\$1.42	4
646.612	TEMPORARY 4 INCH YELLOW LINE, PAINT	LF	\$0.10	73
646.620	TEMPORARY 6 INCH WHITE LINE	LF	\$0.09	5
646.6211	TEMPORARY 6 INCH WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	LF	\$1.17	7
646.622	TEMPORARY 6 INCH WHITE LINE, PAINT	LF	\$0.09	28
646.630	TEMPORARY 6 INCH YELLOW LINE	LF	\$0.08	4
646.6311	TEMPORARY 6 IN YELLOW LINE, TEMPORARY PAVEMENT MARKING TAPE	LF	\$1.06	6
646.632	TEMPORARY 6 INCH YELLOW LINE, PAINT	LF	\$0.08	24
646.640	TEMPORARY 8 INCH WHITE LINE	LF	\$0.25	1
646.642	TEMPORARY 8 INCH WHITE LINE, PAINT	LF	\$0.54	25
646.650	TEMPORARY 8 INCH YELLOW LINE	LF	\$0.77	5
646.652	TEMPORARY 8 INCH YELLOW LINE, PAINT	LF	\$0.55	21
646.660	TEMPORARY 12 INCH WHITE LINE	LF	\$1.20	5
646.6611	TEMPORARY 12 IN WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	LF	\$1.76	5
646.662	TEMPORARY 12 INCH WHITE LINE, PAINT	LF	\$0.39	19
646.672	TEMPORARY 12 INCH YELLOW LINE, PAINT	LF	\$1.55	4

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
646.680	TEMPORARY 24 INCH STOP BAR	LF	\$2.87	12
646.6811	TEMPORARY 24 INCH STOP BAR, TEMPORARY PAVEMENT MARKING TAPE	LF	\$8.83	7
646.682	TEMPORARY 24 INCH STOP BAR, PAINT	LF	\$2.05	71
646.690	TEMPORARY LETTER OR SYMBOL	EACH	\$24.86	11
646.6911	TEMPORARY LETTER OR SYMBOL, TEMPORARY PAVEMENT MARKING TAPE	EACH	\$92.21	2
646.692	TEMPORARY LETTER OR SYMBOL, PAINT	EACH	\$16.83	69
646.700	TEMPORARY CROSSWALK MARKING	LF	\$8.08	4
646.702	TEMPORARY CROSSWALK MARKING, PAINT	LF	\$3.32	32
646.710	TEMPORARY RAILROAD CROSSING SYMBOL	EACH	\$163.07	1
646.712	TEMPORARY RAILROAD CROSSING SYMBOL, PAINT	EACH	\$169.75	20
646.75	RAISED PAVEMENT MARKERS, TYPE II	EACH	\$2.81	5
646.76	LINE STRIPING TARGETS	EACH	\$0.73	104
646.81	PAINTED CURB	LF	\$1.34	19
646.82	PAINTED ISLAND	SF	\$1.00	4
646.85	REMOVAL OF EXISTING PAVEMENT MARKINGS	SF	\$0.42	49
646.86	PAVEMENT MARKING MASK	SF	\$3.36	21
649.11	GEOTEXTILE FOR ROADBED SEPARATOR	SY	\$1.60	53
649.21	GEOTEXTILE UNDER RAILROAD BALLAST	SY	\$4.87	17
649.31	GEOTEXTILE UNDER STONE FILL	SY	\$2.51	177
649.41	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	SY	\$4.04	4
649.51	GEOTEXTILE FOR SILT FENCE	SY	\$4.13	135
649.515	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	SY	\$10.59	90
649.61	GEOTEXTILE FOR FILTER CURTAIN	SY	\$15.88	77
651.15	SEED	LB	\$7.66	251
651.17	SEED, WINTER RYE	LB	\$4.28	62
651.18	FERTILIZER	LB	\$3.75	248
651.20	AGRICULTURAL LIMESTONE	TON	\$539.70	246
651.25	HAY MULCH	TON	\$597.15	245
651.29	STRAW MULCH	TON	\$455.33	3
651.35	TOPSOIL	CY	\$30.96	238
651.40	GRUBBING MATERIAL	SY	\$5.25	145
652.10	EPSC PLAN	LS	\$3,661.94	166
652.20	MONITORING EPSC PLAN	HR	\$37.22	166
652.30	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	LU	\$208.07	166
653.20	TEMPORARY EROSION MATTING	SY	\$2.20	222
653.21	PERMANENT EROSION MATTING	SY	\$5.40	13

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
653.25	TEMPORARY STONE CHECK DAM, TYPE I	CY	\$44.10	72
653.30	PREFABRICATED CHECK DAM	EACH	\$295.79	2
653.35	VEHICLE TRACKING PAD	CY	\$50.15	154
653.40	INLET PROTECTION DEVICE, TYPE I	EACH	\$199.16	79
653.41	INLET PROTECTION DEVICE, TYPE II	EACH	\$180.85	8
653.45	FILTER BAG	EACH	\$367.74	46
653.50	BARRIER FENCE	LF	\$2.03	104
653.55	PROJECT DEMARCATION FENCE	LF	\$1.17	169
653.60	EROSION LOG	LF	\$3.36	35
653.65	LIVE FASCINE	LF	\$19.00	1
653.70	LIVE STAKE	EACH	\$6.00	1
656.16	DECIDUOUS SEEDLINGS	EACH	\$81.47	2
656.20	EVERGREEN TREES	EACH	\$161.11	10
656.25	EVERGREEN SHRUBS	EACH	\$73.38	4
656.30	DECIDUOUS TREES	EACH	\$289.14	17
656.35	DECIDUOUS SHRUBS	EACH	\$49.95	11
656.40	GROUND COVERS AND VINES	EACH	\$5.72	4
656.41	PERENNIALS	EACH	\$8.77	2
656.45	TRANSPLANTING TREES	EACH	\$500.51	2
656.50	TRANSPLANTING SHRUBS	EACH	\$193.43	2
656.55	TRANSPLANTING GROUNDCOVER	SY	\$34.00	1
656.65	LANDSCAPE WATERING	MGAL	\$50.05	13
656.80	LANDSCAPE BACKFILL, TRUCK MEASUREMENT	CY	\$34.35	19
656.85	TREE PROTECTION	LS	\$3,350.49	16
660.10	TIMBER PAINTING, ENVIRONMENTAL PROTECTION	LS	\$2,190.00	2
660.20	TIMBER PAINTING, FIRE RETARDANT	LS	\$13,133.50	2
660.30	TIMBER PAINTING, INSECTICIDE/FUNGICIDE	LS	\$6,567.00	2
661.10	METAL ROOFING	SY	\$78.51	4
675.20	TRAFFIC SIGNS, TYPE A	SF	\$12.20	210
675.21	TRAFFIC SIGNS, TYPE B	SF	\$17.27	13
675.301	FLANGED CHANNEL SIGN POST	LF	\$9.82	3
675.31	W-SHAPE STEEL SIGN POST	LB	\$2.09	4
675.32	TUBULAR ALUMINUM SIGN POST	LB	\$6.78	3
675.33	TUBULAR STEEL SIGN POST	LB	\$2.89	49
675.341	SQUARE TUBE SIGN POST AND ANCHOR	LF	\$7.45	209
675.41	FOUNDATION FOR W-SHAPE STEEL POST, 24 INCH DIAMETER	EACH	\$1,667.50	4
675.42	FOUNDATION FOR W-SHAPE STEEL POST, 30 INCH DIAMETER	EACH	\$2,440.00	1

Vermont Agency of Transportation
5 Year Averaged Price List - ENGLISH
July 2012 - June 2017
2011 Specifications

Item Number	Item Description	Units	Average Price	Contract Occur.
675.43	FOUNDATION FOR TUBULAR STEEL POST	EACH	\$1,033.49	49
675.50	REMOVING SIGNS	EACH	\$11.31	205
675.60	ERECTING SALVAGED SIGNS	EACH	\$26.98	139
675.61	SETTING SALVAGED POSTS	EACH	\$85.88	27
676.10	DELINEATOR WITH STEEL POST	EACH	\$50.21	125
676.12	REMOVAL OF EXISTING DELINEATOR	EACH	\$1.67	63
676.15	REMOVE AND REPLACE REFLECTOR UNIT	EACH	\$5.84	14
676.20	DELINEATOR WITH FLEXIBLE POST	EACH	\$71.50	1
677.12	OVERHEAD TRAFFIC SIGN SUPPORT, CANTILEVER	EACH	\$42,300.00	2
677.13	OVERHEAD TRAFFIC SIGN SUPPORT, MULTI-SUPPORT	EACH	\$78,787.50	3
677.25	REMOVE AND RESET OVERHEAD TRAFFIC SIGN SUPPORT	EACH	\$10,580.00	1
677.30	REMOVE EXISTING OVERHEAD SIGN ASSEMBLY, CANTILEVER	EACH	\$3,816.67	3
677.35	REMOVE EXISTING OVERHEAD SIGN ASSEMBLY, MULTI-SUPPORT	EACH	\$3,637.14	6
678.15	TRAFFIC CONTROL SIGNAL SYSTEM, INTERSECTION	EACH	\$119,975.35	22
678.16	FLASHING BEACON, GROUND MOUNTED	EACH	\$17,265.00	1
678.21	ELECTRICAL CONDUIT	LF	\$12.52	17
678.22	VEHICLE LOOP DETECTOR	LF	\$14.13	5
678.23	WIRED CONDUIT	LF	\$18.04	34
678.24	ELECTRICAL WIRING	LF	\$18.80	2
678.25	PULL BOX, STANDARD	EACH	\$2,032.41	15
678.26	JUNCTION BOX	EACH	\$740.32	14
678.27	PULL BOX, DOUBLE	EACH	\$4,340.00	3
678.30	ELECTRICAL CONDUIT SLEEVE	LF	\$52.63	13
678.40	TEMPORARY TRAFFIC SIGNAL SYSTEM	EACH	\$29,187.82	14
678.42	TEMPORARY DETECTOR	EACH	\$1,000.00	2
678.45	REMOVAL OF EXISTING TRAFFIC CONTROL SIGNAL SYSTEM	EACH	\$6,009.42	9
679.24	REMOVE STREET LIGHT ASSEMBLY	EACH	\$1,634.96	2
679.25	REMOVE AND RESET LIGHT POLE	EACH	\$4,062.09	4
679.45	LIGHT POLE	EACH	\$2,086.90	12
679.46	STREET LIGHT ASSEMBLY	EACH	\$7,307.55	5
679.47	BRACKET ARM	EACH	\$2,781.53	23
679.50	LUMINAIRE	EACH	\$2,007.34	12
679.54	STREET LIGHT CONTROL DEVICE	EACH	\$1,532.14	3
679.55	POWER DROP STANCHION, STREET LIGHTING	EACH	\$3,948.36	16
690.50	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	LU	\$54.19	159