LETTING DATE : 06/26/20 11:00 A.M.

CONTRACT ID : 18H284
PROJECT(S) : MORRISTWON AV-FY19-011 (RE-AD)

ITEM NO.	LINE NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001				
900.608	0005	SPECIAL PROVISION (FAA M-002 CONTAMINATED SOIL REMOVAL AND REPLACEMENT)	5.000	CY
900.608	0010	SPECIAL PROVISION (FAA P-152 EMBANKMENT IN PLACE)	2,850.000	CY
900.608	0015	SPECIAL PROVISION (FAA P-152 UNCLASSIFIED EXCAVATION)	26,000.000	CY
900.608	0020	SPECIAL PROVISION (FAA P-154 SUBBASE COURSE)	7,400.000	CY
900.608	0025	SPECIAL PROVISION (FAA P-209 CRUSHED AGGRE BASE COURSE)	2,150.000	CY
900.620	0030	SPECIAL PROVISION (FAA C-102 INLET PROTECTION)	8.000	EACH
900.620	0035	SPECIAL PROVISION (FAA D-751 4-FT DIAMETER CATCH BASIN)	5.000	EACH
900.620	0040	SPECIAL PROVISION (FAA D-751 4-FT DIAMETER DRAIN MANHOLE)	3.000	EACH
900.620	0045	SPECIAL PROVISION (FAA D-751 6-FT DIAMETER CATCH BASIN)	2.000	EACH
900.620	0050	SPECIAL PROVISION (FAA D-751 6-FT DIAMETER DRAIN MANHOLE)	3.000	EACH
900.620	0055	SPECIAL PROVISION (FAA L-115 REMOVE ELECTRICAL HANDHOLE)	2.000	EACH
900.620	0060	SPECIAL PROVISION (FAA L-125 REMOVE ELEVATED STAKE MOUNTED RETROREFLECTIVE MARKER)	8.000	EACH
900.620	0065	SPECIAL PROVISION (FAA L-125 REMOVE ELEVATED TAXIWAY EDGE LIGHT)	16.000	EACH
900.620	0070	SPECIAL PROVISION (FAA L-125 REMOVE LIGHTED AIRFIELD GUIDANCE SIGN AND FOUNDATION)	2.000	EACH
900.620	0075	SPECIAL PROVISION (FAA P-101 DRAINAGE STRUCTURE REMOVAL)	6.000	EACH
900.620	0080	SPECIAL PROVISION (FAA P-101 TIE-DOWN REMOVAL)	42.000	EACH
900.620	0085	SPECIAL PROVISION (FAA P-101 UNDERDRAIN CLEANOUT REMOVAL)	4.000	EACH
900.625	0090	SPECIAL PROVISION (FAA P-603 EMULSIFIED ASPHALT TACK COAT)	950.000	GAL
900.640	0095	SPECIAL PROVISION (FAA C-102 BARRIER FENCE)	2,000.000	LF
900.640	0100	SPECIAL PROVISION (FAA C-102 STRAW WATTLES)	2,200.000	LF
900.640	0105	SPECIAL PROVISION (FAA D-701 12-INCH HDPE PIPE)	250.000	LF
900.640	0110	SPECIAL PROVISION (FAA D-701 12-INCH RCP)	200.000	LF
900.640	0115	SPECIAL PROVISION (FAA D-701 15-INCH HDPE PIPE)	50.000	LF
900.640	0120	SPECIAL PROVISION (FAA D-701 15-INCH RCP)	150.000	LF
900.640	0125	SPECIAL PROVISION (FAA D-701 18-INCH HDPE PIPE WITH STONE)	450.000	LF
900.640	0130	SPECIAL PROVISION (FAA D-701 24-INCH RCP)	100.000	LF
900.640	0135	SPECIAL PROVISION (FAA D-701 36-INCH HDPE PIPE WITH STONE)	400.000	LF
900.640	0140	SPECIAL PROVISION (FAA D-701 6" HDPE PIPE)	50.000	LF
900.640	0145	SPECIAL PROVISION (FAA L-108 REMOVE CABLE)	1,770.000	LF
900.640	0150	SPECIAL PROVISION (FAA L-110 REMOVE CONDUIT)	1,470.000	LF
900.640	0155	SPECIAL PROVISION (FAA P-101 PIPE REMOVAL)	1,200.000	LF
900.640	0160	SPECIAL PROVISION (FAA P-101 UNDERDRAIN REMOVAL)	700.000	LF
900.640	0165	SPECIAL PROVISION (FAA P-605 JOINT SEALING FILLER)	1,450.000	LF
900.645	0170	SPECIAL PROVISION (FAA C-100 CONTRACTOR QUALITY CONTROL PROGRAM (CQCP))	1.000	LUMP
900.645	0175	SPECIAL PROVISION (FAA C-102 SEDIMENT AND EROSION CONTROL)	1.000	LUMP
900.645	0180	SPECIAL PROVISION (FAA C-102 SEDIMENTATION CONTROL INSPECTION AND REPORTING)	1.000	LUMP
900.645	0185	SPECIAL PROVISION (FAA C-105 MOBILIZATION (5% MAX.))	1.000	LUMP
900.645	0190	SPECIAL PROVISION (FAA F-001 EXISTING FUEL SYSTEM REMOVAL)	1.000	LUMP
900.645	0195	SPECIAL PROVISION (FAA G-001 CONTRACTOR'S SAFETY PLAN COMPLIANCE DOCUMENT (SPCD))	1.000	LUMP

LETTING DATE : 06/26/20 11:00 A.M.

CONTRACT ID : 18H284
PROJECT(S) : MORRISTWON AV-FY19-011 (RE-AD)

ITEM NO.	LINE NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001				
900.645	0200	SPECIAL PROVISION (FAA G-001 SAFETY AND PHASING)	1.000	LUMP
900.645	0205	SPECIAL PROVISION (FAA G-002 AS-BUILT PLANS AND FINAL SURVEY)(N. A.B.I.)	1.000	LUMP
900.670	0210	SPECIAL PROVISION (FAA P-620 SURFACE PREPARATION)	1,300.000	SF
900.670	0215	SPECIAL PROVISION (FAA P-620 TEMPORARY MARKING)	2,450.000	SF
900.675	0220	SPECIAL PROVISION (FAA C-102 ROLLED EROSION CONTROL MATTING)	5,600.000	SY
900.675	0225	SPECIAL PROVISION (FAA P-101 PAVEMENT REMOVAL)	6,500.000	SY
900.675	**0230**	**SPECIAL PROVISION (FAA P-501 PORTLAND CEMENT CONCRETE PAVEMENT)**	**370.000**	**SY**
900.675	0235	SPECIAL PROVISION (FAA T-901 SEEDING)	1,800.000	SY
900.675	0240	SPECIAL PROVISION (FAA T-905 TOPSOILING 4" DEPTH)	19,850.000	SY
900.680	0245	SPECIAL PROVISION (FAA P-401 ASPHALT SURFACE COURSE)	2,500.000	TON
SECTION NO. 0002				
900.620	0250	SPECIAL PROVISION (FAA D-705 NEW UNDERDRAIN CLEANOUT, COMPLETE)	16.000	EACH
900.640	0255	SPECIAL PROVISION (FAA D-705 6-INCH PIPE UNDERDRAIN, COMPLETE)	3,300.000	LF
SECTION NO. 0003				
900.620	0260	SPECIAL PROVISION (FAA L-125 NEW L858 LIGHTED AIRFIELD GUIDANCE SIGN, 1 MODULE)	6.000	EACH
900.620	0265	SPECIAL PROVISION (FAA L-125 NEW L858 LIGHTED AIRFIELD GUIDANCE SIGN, 2 MODULE)	3.000	EACH
900.620	0270	SPECIAL PROVISION (FAA L-125 NEW L858 LIGHTED AIRFIELD GUIDANCE SIGN, 3 MODULE)	2.000	EACH
900.620	0275	SPECIAL PROVISION (FAA L-125 NEW L861 BI-DIRECTIONAL RUNWAY EDGE LIGHT)	1.000	EACH
900.620	0280	SPECIAL PROVISION (FAA L-125 NEW L861T ELEVATED TAXIWAY EDGE LIGHT)	73.000	EACH
900.640	0285	SPECIAL PROVISION (FAA L-108 NO. 6 AWG, SLD, BARE COPPER C NTRPOISE WIRE, INST IN TRNCH CONN/TERM)	1,200.000	LF
900.640	0290	SPECIAL PROVISION (FAA L-108 NO. 8 AWG, 5 KV, L-824, TYPE C CABLE, INST IN DUCT BANK OR CONDUIT)	5,600.000	LF
900.640	0295	SPECIAL PROVISION (FAA L-110 CONCRETE ENCASED ELECTRICAL CONDUIT, 1-WAY 2-INCH, PVC SCHEDULE 40)	330.000	LF
900.640	0300	SPECIAL PROVISION (FAA L-110 CONCRETE ENCASED ELECTRICAL D UCT BANK, 4-WAY 3-INCH, PVC SCHEDULE 40)	85.000	LF
900.640	0305	SPECIAL PROVISION (FAA L-110 NON-ENCASED ELECTRICAL CONDUIT, 1-WAY 2-INCH, PVC SCHEDULE 40)	4,100.000	LF
900.645	0310	SPECIAL PROVISION (FAA L-109 WORK IN LIGHTING VAULT)	1.000	LUMP
SECTION NO. 0004				
900.670	0315	SPECIAL PROVISION (FAA P-620 BLACK PAINT)	1,600.000	SF
900.670	0320	SPECIAL PROVISION (FAA P-620 PERMANENT MARKING)	2,400.000	SF

LETTING DATE : 06/26/20 11:00 A.M.

CONTRACT ID : 18H284
PROJECT(S) : MORRISTWON AV-FY19-011 (RE-AD)

ITEM NO.	LINE NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005				
900.675	0325	SPECIAL PROVISION (FAA T-901 SEEDING)	18,050.000	SY
SECTION NO. 0006				
900.645	0330	SPECIAL PROVISION (FAA C-105 ENGINEER'S FIELD OFFICE)	1.000	LUMP
SECTION NO. 0007				
900.645	0335	SPECIAL PROVISION (FAA G-002 AERIAL PHOTOGRAPHS)	1.000	LUMP
SECTION NO. 0008				
900.645	0340	SPECIAL PROVISION (FAA G-002 GIS CONVERSION)(N.A.B.I.)	1.000	LUMP
SECTION NO. 0009				
900.620	0345	SPECIAL PROVISION (FAA L-115 NEW AIRCRAFT RATED ELECTRICAL HANDHOLE (4'X4'))	7.000	EACH
900.640	0350	SPECIAL PROVISION (FAA L-108 NO. 2 AWG, 600V, INSUL EQUIP GROUND, INST IN DUCT BANK OR CONDUIT)	1,200.000	LF
900.640	0355	SPECIAL PROVISION (FAA L-108 NO. 4/0 AWG, 600V CABLE, INSTALLED IN DUCT BANK OR CONDUIT)	3,500.000	LF
900.640	0360	SPECIAL PROVISION (FAA L-110 CONCRETE ENCASED ELECTRICAL D UCT BANK, 4-WAY 3-INCH, PVC SCHEDULE 40)	1,115.000	LF
900.640	0365	SPECIAL PROVISION (FAA L-110 GALVANIZED RIGID STEEL CONDUIT, 2-WAY 3-INCH)	10.000	LF
900.645	0370	SPECIAL PROVISION (FAA F-001 NEW FUEL SYSTEM - CONCRETE PAD AND SELECT MATERIALS)	1.000	LUMP
900.645	0375	SPECIAL PROVISION (FAA L-109 FUEL FARM SERVICE)	1.000	LUMP
SECTION NO. 0010				
900.645	0380	SPECIAL PROVISION (FAA F-001 NEW FUEL SYSTEM - SYSTEM COMPONENTS)	1.000	LUMP
SECTION NO. 0011				
900.645	0385	SPECIAL PROVISION (FAA M-003 MAINTENANCE OF TRAFFIC)	1.000	LUMP