Housekeeping Items



- Meeting is being recorded and will be posted on the project website
- Everyone is muted



For those joining us by computer or web browser

Questions may be entered in the Q&A Window at any time (button appears the bottom of the screen) please include your email address



For those joining us by phone

Press *9 to raise your hand to be called on during the question-and-answer session following the presentation



For those joining us in person

Please raise your hand and a member of our team will alert you when it's your turn to speak during the question-andanswer session

Project Construction

Burlington's Southern Gateway





Shelburne St. Roundabout

BURLINGTON, VT.

July 1, 2021 Project Information Meeting





Introductions: Project Team

Project Managers

- Michael LaCroix
- Ben Tietze



- Laura Wheelock
- Olivia Darisse



Public Outreach Officers

- Megan Savage
- Delia Makhetha







Introductions: Project Construction Team



VTrans Construction Staff

- Josh Hulett
- Kara Yelinek



Prime Contractor

- Matt Wheeler
- Brian Mier





Welcome to the Rotary!






Why a Project?

- High Crash Location
 - In 2016, 50 reported crashes in 5 years
 - Has been on every HCL consecutively since at least 1998 (22 years)
- Left Turns: Awkward and tight
- Uncontrolled Drive Accesses
- High presence of bicyclist and pedestrians
 - School and churches are frequent destinations
 - Long existing crosswalks
 - Inadequate number of crosswalks
- Aesthetically unappealing
 - A sea of pavement, Lack of landscaping
 - Not welcoming as a gateway for city







The Solution: The Modern Roundabout







Schedule



- Work begins in Mid-July 2021 (Watch Message Boards & E-Mail updates for actual start date).
- Schedule: Mondays through Fridays typically
- Hours: 7:00 AM 5:30 PM typically
- Saturday work may be allowed for special situations.
- Nighttime work may be allowed for certain construction activities (i.e utility crossings under Shelburne Street).
- Work in winter months as necessary.

Schedule subject to change based on weather and site conditions.

Anticipated Completion: June 2023

Anticipated Construction Impacts No Small Feats



Archaeological

Excavation of historical artifacts by UVM.

Contaminated Soils & Water

- Excavation and transporting off-site of petroleum contaminated soils.
- Excavation of urban soils.
- Dewatering and treating of contaminated groundwater as necessary.

Utilities


- Replace and/or upgrade buried utilities.
- Keeping existing services active, there may be minor shut-offs with <u>48- to 72-hour advanced</u> <u>notification</u>.
- Disconnect and remove or abandon old services after new services are installed.

Challenges to Implementation No Small Feats



Contaminated Soils & Water

- Petroleum
 - 4 Fueling Stations at some point in the past (1 still exists)
 - Century 21, Majestic Car Rental and Former Rotary Gulf
- Urban Background Development Soils
 - Throughout the site



Challenges to Implementation



Contaminated Soils & Water

- Contaminated Soils will be collected and transported off-site:
 - To Landfill
 - To Incinerator
- There will be no stockpiling of contamination on-site. Only clean material *may* be stockpiled.
- Baffled fractionalization tanks will be on site to filter/settle contaminated groundwater as necessary.




Challenges to Implementation No Small Feats

Shelburne St. Roundabout BURLINGTON, VT.

Utilities

- 37,000 ft (~7 miles) of existing utiliti
- Some active, some abandoned
 - Gas
 - Water
 - Sewer
 - Storm
 - Electric
 - Telephone
 - Telecom
 - Fiber
 - Cable TV




Challenges to Implementation



Proposed Utilities

- Utility Duct Banks (Concrete-Encased).
- New water line, sewer, storm utils.
- Keep existing utilities active until new utilities are constructed.
- Private Utilities may reach out to customers.
- Water, Sewer, Storm, Electric disruptions will be announced in advance.



Large-Scale Construction Impacts Be Alert!



Ledge/Bedrock

- Shallow in places.
- Ledge is geologically hard.

Transportation Management


- Many construction phases.
- Multiple construction crews simultaneously working.
- Maintain open access to drives to residences and businesses.

Challenges to Implementation



<u>Transportation Management</u>

- Maintain pedestrian and bicycle accommodations through construction.
- Detours for certain construction phases.
- Restrict Left Turns during construction (for certain phases).
- Comprehensive Construction Phasing/Sequencing Plan (photo).
- Coordinate with CKS for <u>potential</u> alternative student drop-off/pick-up.
- New temporary crosswalk crossing Shelburne Street at Adams Court.
- Dust will be controlled/managed.




Challenges to Implementation No Small Feats



Ledge/Bedrock

- Borings located it at depths of 2'-17' generally. Several knobs visible at surface throughout.
- Blasting and hammering anticipated.
- In close proximity of houses and businesses.



Challenges to Implementation No Small Feats



Ledge/Bedrock

- Pre-Blast Survey
 - Within 500' of the project limits.
 - SD Ireland personnel will document structural conditions prior to blasting or hammering activities.

Construction Vibration Monitoring

- Pre-Construction Survey
 - Within 150' of the project limits
 - SD Ireland and Alpha Testing will document structural conditions prior to construction activities.





Challenges to Implementation No Small Feats



Ledge/Bedrock

- Pre-Blast/Construction Vibration Survey
 - If you live within, on, or touching this circle and are willing to provide SD Ireland contact information so that they can access your building or home to conduct the Pre-Blast & Construction Vibration Survey, please provide your information in the Q&A window in this webinar.
 - Or call the toll-free number or e-mail the team your information: (802) 496-8956
 - Your information will only be visible to project team staff and will not be shared; destroyed after completion of surveys.





WSP USA, Inc.

- Hired by VTrans
- In direct communication with VTrans and DPW
- Will be participating in <u>WEEKLY</u> meetings with the construction contractor and VTrans construction staff
 - Issue weekly Construction Updates & Traffic Alerts
 - Manages Telephone Hotline & Project E-Mail
 - Take comments from public
 - Responds to questions directly or distributes to appropriate party for response
 - Maintain the project website & info materials
 - Door-to-door outreach in advance of utility outages

This is the **FASTEST** path for information to residents, businesses and commuters.






→115D → §

Hotline: 802-496-8956 info@shelburnestreetroundabout.com

The Public

Commuters

commoters



Shelburne Street Roundabout Project

Questions?







For those joining us by computer or web browser

Please enter questions in the Q&A Window. The button appears the bottom of the screen - please include your email address



For those joining us by phone

Press *9 to raise your hand to be called on by the host. When directed by the host, please press *6 to unmute yourself



For those joining us in person

Please raise your hand and a member of our team will alert you when it is your turn to speak

Stay Involved





Visit the Project Website:

https://vtrans.vermont.gov/projects/burlington-roundabout

Sign Up Here for E-Mail Notifications on Construction Updates and Traffic Alerts



Email Us:

info@shelburnestreetroundabout.com



Call the 24-Hour Project Hotline: 802-496-8956